

## **General Disclaimer**

### **One or more of the Following Statements may affect this Document**

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.

(NASA-CR-165509) MAGNETOHYDRODYNAMICS (MHD)  
ENGINEERING TEST FACILITY (ETF) 200 MWE  
POWER PLANT. CONCEPTUAL DESIGN ENGINEERING  
REPORT (CDER) SUPPLEMENT. MAGNET SYSTEM  
SPECIAL INVESTIGATIONS Final (Massachusetts G3/37

N83-14494

Unclas  
02291

DOE/NASA/0100-1  
NASA CR-165509


## **Magnetohydrodynamics (MHD) Engineering Test Facility (ETF) 200 MWe Power Plant**

**Conceptual Design Engineering Report (CDER) Supplement**

**Magnet System Special Investigations**

**Massachusetts Institute of Technology  
Francis Bitter National Magnet Laboratory**

**September 1981**



Prepared for  
National Aeronautics and Space Administration  
Lewis Research Center  
Under Grant NAG 3-100

for  
**U.S. DEPARTMENT OF ENERGY  
Fossil Energy  
Office of Magnetohydrodynamics**

DOE/NASA/0100-1  
NASA CR-165509

**Magnetohydrodynamics (MHD)  
Engineering Test Facility (ETF)  
200 MWe Power Plant**

**Conceptual Design Engineering Report (CDER) Supplement**

**Magnet System Special Investigations**

**Massachusetts Institute of Technology  
Francis Bitter National Magnet Laboratory  
Cambridge, MA 02139**

**September 1981**

Prepared for  
National Aeronautics and Space Administration  
Lewis Research Center  
Cleveland, Ohio 44135  
Under Grant NAG 3-100

for  
**U.S. DEPARTMENT OF ENERGY  
Fossil Energy  
Office of Magnetohydrodynamics  
WASHINGTON, D.C. 20545  
UNDER INTERAGENCY AGREEMENT DE-A101-77ET10769**

MHD-ETF  
CONCEPTUAL DESIGN  
ENGINEERING REPORT

ORIGINAL PAGE IS  
OF POOR QUALITY

TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>	<u>Page</u>
1.0	INTRODUCTION	1
2.0	4 TESLA MAGNET DESIGN	1
2.1	DESIGN SUMMARY	1
2.2	DESIGN DESCRIPTION	2
2.2.1	<u>Windings and Substructure</u>	9
2.2.2	<u>Conductor</u>	9
2.2.3	<u>Winding Containment Vessels</u>	11
2.2.4	<u>Main Force Containment Structure</u>	11
2.2.5	<u>Thermal Radiation Shield</u>	11
2.2.6	<u>Low Heat Leak Supports</u>	12
2.2.7	<u>Vacuum Jacket and Warm Bore</u>	12
2.2.8	<u>Water-Cooled Warm Bore Liner</u>	12
2.2.9	<u>Vapor Cooled Electrical Leads</u>	12
	<u>Internal Instrumentation, etc.</u>	12
2.2.10	<u>Roll-Aside System</u>	12
2.2.11	<u>Cryogenic Support Equipment</u>	12
2.2.12	<u>Vacuum Pumping Equipment, Protection/Control</u>	13
	<u>and Instrumentation</u>	13
2.2.13	<u>Power Supply and Discharge Equipment</u>	13
2.3	COST ESTIMATE, 4 T MAGNET SYSTEM	13
3.0	6 TESLA MAGNET MANUFACTURABILITY STUDY	16
3.1	SUMMARY	17
3.2	CONCLUSIONS	18
3.3	DISCUSSION	13
3.3.1	<u>Evolution of the ETF Magnet Conceptual Design</u>	18
3.3.2	<u>Alternative Concepts</u>	20
3.3.3	<u>Revisions to the ETF Magnet to Improve</u>	21
	<u>Manufacturability</u>	21
3.3.4	<u>Drawings</u>	22
3.4	REVISED SCHEDULE, 6 T MAGNET SYSTEM	22
3.5	REVISED COST ESTIMATE, 6 T MAGNET SYSTEM	22
3.6	REVISED WEIGHT ESTIMATE, 6 T MAGNET SYSTEM	26
	REFERENCES	27

LIST OF TABLES

<u>Table Number</u>	<u>Title</u>	<u>Page</u>
2.1	Major Characteristics and Estimated Costs - 4 T and 6 T Magnet Systems	1,2
2.2	4 T Magnet System - Magnet Design Characteristics	6,7
2.3	4 T Magnet System - Utility Requirements	8
2.4	4 T Magnet - Conductor (Cable) Characteristics	9,11
2.5	4 T Magnet System - Power Supply and Discharge System Characteristics	14
2.6	Summary Cost Estimate - ETF 4 T Magnet System Conceptual Design	15
3.1	Summary Cost Estimate - ETF 6 T Magnet System Conceptual Design (Revised)	24
3.2	Cost Estimate Breakdown - ETF 6 T Magnet System Conceptual Design (Revised)	25

LIST OF FIGURES

<u>Figure Number</u>	<u>Title</u>	<u>Page</u>
2.1	4 T Magnet Outline	3
2.2	4 T Magnet Field Profile	4
2.3	4 T Magnet Fringe Field Zone Boundaries	5
2.4	4 T Magnet Winding Envelope	10
3.1	Critical Path Schedule - 6 T Magnet System (Revised)	23

LIST OF ATTACHMENTS

Attachment A - Manufacturability Report, MHD-ETF 200 MWe Power Plant Magnet System Conceptual Design, by Combustion Engineering, Inc., September, 1981.

Attachment B - Drawings of ETF 6 T Magnet Components (Revised).

ORIGINAL PAGE IS  
OF POOR QUALITY

## 1.0 INTRODUCTION

This report supplement summarizes the results of two special investigations made by Massachusetts Institute of Technology, Francis Bitter National Laboratory (FBNML) as a part of the overall conceptual design study of the MHD/ETF for which NASA LeRC has management responsibility. The two investigations, included in FBNML's Phase II effort by letter agreement<sup>9</sup> under NASA LeRC Grant NAG-3-100, are the 4 Tesla Magnet Alternate Design Study (Task 1 of reference letter), and the 6 Tesla Magnet Manufacturability Study (Task 2 of reference letter).

These investigations supplement the 6 T magnet system conceptual design work performed by FBNML and reported in Section SDD503 of the ETF Conceptual Design Engineering Report (CDER).<sup>1</sup>

## 2.0 4 TESLA MAGNET ALTERNATE DESIGN

A 4 tesla superconducting magnet system conceptual design was prepared by FBNML for NASA LeRC's use in their investigation of an alternate (supersonic) power train for the ETF.

Design work was initiated in August, 1981, upon receipt of requirements from NASA LeRC. Specified were a peak field of 4 tesla with a field profile shape, active length, and warm bore dimensions the same as those of the 6 T magnet design prepared by FBNML for NASA LeRC and described in the ETF Conceptual Design Engineering Report (CDER), System Design Description SDD503. (The 6 T magnet is intended for use in a subsonic power train.)

The 4 T magnet system design, described below, derived by scaling techniques from the 6 T magnet design, is intended to establish approximate system characteristics only, and is not optimized. Should NASA LeRC investigations and/or other studies show the alternate (supersonic) power train to be sufficiently attractive to warrant further examination, the 4 T magnet system design should be investigated in greater depth.

## 2.1 DESIGN SUMMARY

The major characteristics and estimated cost of the 4 T magnet system design compared to the original 6 T design are listed in Table 2.1

TABLE 2.1  
Major Characteristics and Estimated Costs  
4 T and 6 T Magnet Systems

	4 T Design (Scaled)	6 T Design (SDD503)
Peak on-axis field	4 T	6 T
Active Length	12.1 m (39' 3")	12.1 m (39' 8")

**ORIGINAL PAGE IS  
OF POOR QUALITY**

TABLE 2.1 (continued)

	<u>4 T Design (Scaled)</u>	<u>6 T Design (SDD503)</u>
Field at start of active length	2.67 T	4 T
Field at end of active length	2.33 T	3.5 T
Aperture* at start of active len.	55" x 71 "	55" x 71"
Aperture* at end of active length	81" x 106"	81" x 106"
Magnet overall length	54' 4"	54' 4"
Magnet outside diameter	26' 0"	27' 6"
Magnet weight	1.25 x 10 <sup>6</sup> lbs	2 x 10 <sup>6</sup> lbs
Magnet system estimated cost**	\$47 x 10 <sup>6</sup>	\$58 x 10 <sup>6</sup>

\* aperture dimensions are inside water-cooled warm bore liner

\*\* cost estimates are based on conceptual design as it existed prior to the manufacturability study described in Section 3.0 of this report

Outline dimensions of the 4 T magnet are shown in Fig. 2.1, the field profile is shown in Fig. 2.2 and fringe magnetic field zone boundaries (personnel exclusion zones) are shown in Fig. 2.3.

The design characteristics of the magnet system are listed in Table 2.2 and the utility requirements in Table 2.3.

## 2.2 DESIGN DESCRIPTION

Consistent with requirements given by NASA LeRC, the 4 T magnet retains the same warm bore aperture dimensions, the same shape of field profile and the same overall length as the 6 T magnet from which it has been scaled.

Also, it retains the same type of winding (60° rectangular saddle), the same type of conductor (circular cable), substantially the same design current (~ 25,000 A) and similar designs of substructure, superstructure and cryostat.

In scaling down to the 4 T field strength, ampere-turns and structural requirements are substantially reduced, so the magnet becomes smaller in diameter, lighter in weight and less expensive, both in material, fabrication and assembly cost.

In the following paragraphs, the design of components is described and scaling of the components of the magnet and of the accessory systems is discussed.

1. NOTE: SOME CROSS-SECTION DIMENSIONS ARE INSIDE WARM BORE LINER
2. DIMENSIONS ARE IN FEET EXCEPT WHERE OTHERWISE NOTED
3. WELD-DOWN BRACKET'S ARE DESIGNED TO HOLD MACHINERY FIRMLY IN PLACE IN "OPERATING" POSITION WHEN WILL BE DISCHARGED WHEN MACHINERY IS TO BE ROLLED AWAY

Technical drawing of a plasma torch assembly, showing three views: Plan View, Section A-A, and Elevation VII-V.

**Plan View:** Shows the top-down layout of the assembly. Key dimensions include a total width of 34'-0" and a total length of 63'-3". A central section is labeled "CHANNEL ACTIVE LENGTH" with a dimension of 47'-0" (12.1m). A "TRACK BASE PLATE" is indicated on the left side. The drawing is labeled "PLAN VIEW" at the bottom.


**Section A-A:** Shows a cross-section of the assembly. Key dimensions include a total width of 15'-5" and a total height of 11'-0" (2.6m). The drawing is labeled "SECTION A-A" at the bottom.

**Elevation VII-V:** Shows the side view of the assembly. Key dimensions include a total width of 13'-4" and a total height of 42'-3". The drawing is labeled "ELEVATION VII-V" at the bottom. It includes labels for "INLET", "EXIT", "PLASMA FLOW", "STIFFENERS", "HOLD DOWN BRACKET (TYP)", and "SEE NOTE 1".

**Figure 2.1**  
**4 T Magnet Outline**

**F1113**





ORIGINAL PAGE IS  
OF POOR QUALITY

Figure 2.2  
4 T Magnet Field Profile

"A1112

NOTES:

- 1 LINES OF CONSTANT MAGNETIC FRINGE FIELD ARE INDICATED BY - - - - -
- 2 CRITERIA FOR PERSONNEL EXPOSURE TO MAGNETIC FIELD ARE FURTHER DEFINED IN MHD ETF 200 MWE POWER PLANT MAGNET SYSTEM DESIGN DESCRIPTION, APPENDIX A (SPECIFICATION A-4442) IN SDD-503
- 3 MAGNET WILL BE CHARGED ONLY WHEN IN OPERATING POSITION
- 4 MAGNETIC FIELDS ARE IN TESLA (T)

REFERENCE DWG

D-4448 ETF 200 MWE POWER PLANT  
MAGNET SYSTEM PLANT AND  
ELEVATION.

SCALE




Figure 2.3  
Magnet Fringe Field  
Zone Boundaries

TABLE 2.2 Sheet 1 of 2

4 T MAGNET SYSTEM  
MAGNET DESIGN CHARACTERISTICS

## Magnetic Field:

Peak on-axis field	4 T
Active field length	12.1 m (39' 8")
Field at start of active length, $B_{IN}$	2.67 T
Field at end of active length, $B_{EX}$	2.33 T
Peak field in winding	5.3 T

## Dimensions:

Aperture, warm bore inlet*	55" x 71"
Aperture, start of active length*	55" x 71"
Aperture, end of active length*	81" x 106"
Aperture, warm bore exit*	85" x 111"
Length of warm bore	49' 9"
Distance, bore inlet to start of active length	3' 6"
Vacuum vessel overall length, including water-cooled warm bore liner	54' 4"
Vacuum vessel outside diameter	26' 0"

## Winding Characteristics:

Design current	25,000 A
Winding current density	$1.4 \times 10^7$ A/m <sup>2</sup>
LHe to conductor ratio (volume)	1.1
Ampere turns	$18 \times 10^6$
Ampere meters	$7 \times 10^8$
Inductance	4.2 henries
Stored energy	1300 MJ

## Winding Dimensions:

Depth (build), winding cross-section	25"
Height, winding cross-section, one quadrant	40.7"
Gap (distance from winding to bore surface inside warm bore liner)	16.7"

\*Inside water-cooled warm bore liner

TABLE 2.2 Sheet 2 of 2

Conductor:

Type	Cable
S.C. material	NbTi
Overall diameter	1.0"
Strand diameter	0.046"
Cu/SC in high field regions	12
Total length conductor	93,000'

Weights:

Conductor	149,000 lbs.
Insulation	(included in substructure)
Substructure	132,000 lbs.
Superstructure and coil containment vessels	560,000 lbs.
Total cold mass	841,000 lbs.
Thermal radiation shield, cold mass supports, etc.	60,000 lbs.
Vacuum vessel and mounting feet	329,000 lbs.
Miscellaneous	20,000 lbs.
Total Magnet Weight	1,250,000 lbs.

Cryogenic Data:

Operating temperature at winding	4.5 K
Heat leak to LHe region	170 watts
Liquid helium for lead cooling	75 g/hr.

TABLE 2.3  
4 T MAGNET SYSTEM  
UTILITY REQUIREMENTS

Electric Power (60 Hz)

Power supply - Maximum charging	4160 V	1250 KW	3 $\phi$
- Steady state of operation	4160 V	300 KW	3 $\phi$
Refrigerator/liquefier	220 V	10 KW	1 $\phi$
Refrigerator compressors	440 V	500 KW*	3 $\phi$
Utility vacuum pump	220 V	15 KW	3 $\phi$
Diffusion pumps, main vacuum (2)	440 V	24 KW	3 $\phi$
Fore pumps, main vacuum (2)	440 V	20 KW	3 $\phi$
Warm-up heat exchanger	440 V	TBD	3 $\phi$
Hydraulic pump package	440 V	20 KW	3 $\phi$

Cooling Water (80° F max., 50 psig except 100 psig for warm bore liner)

Power supply (rectifiers; diodes)	35 GPM
Discharge resistors	50 GPM
Refrigerator compressors	150 GPM
Refrigerator/liquefier	3 GPM
Diffusion pumps, main vacuum (2)	5 GPM
Fore pumps, main vacuum (2)	5 GPM
Warm bore liner - Steady-state	40 GPM
- Emergency	200 GPM
Water-cooled power bus	30 GPM

Liquid Nitrogen (30 psig)

Cool-down heat exchanger (during cool-down only)	TBD
Refrigerator pre-cooling (steady state)	150 g/hr.**
Magnet radiation shield, transfer lines, etc.(steady-state)	60 g/hr.**

Compressed Air (90 psig)

Refrigerator and vacuum system controls	25 SCFM
---	---------

\* Nominal running power with power factor = 0.9. Starting requires 3 x running power.

\*\* The refrigerator, thermal shield and transfer line LN<sub>2</sub> requirements totaling 210 g/hr (steady state) will be supplied from facility air separation unit.

### 2.2.1 Windings and Substructure

The windings for the 4 T magnet are similar in configuration and substantially the same in overall length and width of straight section as those of the 6 T design. The depth (built) of the winding bundles is reduced to about 2/3, so that the design field of 4 T is produced with about the same overall current density in the windings as that of the 6 T design. The reduced depth results in a reduction in the outside envelope dimensions of the winding end turns.

The windings of the 4 T magnet are more conservative than those of the 6 T design, because more copper is provided relative to the current carried, and the magnetoresistance of the copper is lower because of the lower field in the winding. The cryostatic stability margin is greater than in the 6 T design.

The cable conductor is supported in a substructure of molded glass-reinforced plastic similar in design to that of the 6 T magnet.

The dimensions of the winding envelope for the 4 T magnet are shown in Fig. 2.4.

### 2.2.2 Conductor


The conductor is similar in material, configuration and design current to that of the 6 T magnet, i.e., NbTi/copper cable 1 inch in diameter with 259 strands, part of which are NbTi/copper composite wires (monoliths) and part of which are copper wires. The conductor is in two grades, as in the 6 T magnet, to reduce the total amount of NbTi required.

The maximum field to which the conductor is exposed in the 4 T magnet is lower, and therefore there are fewer strands of composite wire in the conductor and more of copper wire than in the corresponding conductor for the 6 T magnet.

Approximate conductor characteristics are listed in Table 2.4.

TABLE 2.4  
4 T Magnet Conductor (Cable) Characteristics

	<u>Grade A</u>	<u>Grade B</u>
Design current (A)	25,000	25,000
Magnetic field (T)	5.3	3.5
NbTi current density (A/ m <sup>2</sup> )	11.6 x 10 <sup>4</sup>	16.2 x 10 <sup>4</sup>
Total number of strands	259	259
Copper strands	79	115
Composite strands	180	144
Strand diameter (in)	0.046	0.046



A1111

ORIGINAL PAGE IS  
OF POOR QUALITY

Figure 2.4  
4 T Magnet Winding Envelope

TABLE 2.4 (continued)

	<u>Grade A</u>	<u>Grade B</u>
Cu/Sc ratios		
Composite strands	8	8
Overall cable	12	15
Finished length required (ft.)	42,500	50,500
Weight/length, average (lbs/ft)	1.07	1.07

To provide a conservative performance margin, the conductor design current is set at 85% of the specified maximum current capability (critical current) for the cable at the operating temperature of 4.5 K, the same as in the 6 T design.

#### 2.2.3 Winding Containment Vessels

The two winding halves are enclosed in winding containment vessels of the same design and material as those of the 6 T magnet. The wall thickness of the containment vessels is reduced to 1½ inches in the straight section and 2 inches in the end-turn regions (compared to 2 inches and 3 inches, respectively, in the 6 T design). The wall thickness of the vessels is determined in part by their function in containing a portion of the magnetic forces on the windings. The reduction in wall thickness is therefore justified because of the reduction of magnetic forces and pressures (by a factor of roughly 0.45). Reduction of thickness by the full 0.45 factor is not practical, however, because of deflection considerations.

#### 2.2.4 Main Force Containment Structure

The main force containment structure, consisting of welded stainless steel I-beams, threaded tie-rods, nuts and spherical washers, is similar to that of the 6 T magnet except that beam and rod cross-section areas are reduced by a factor of approximately 0.45, in view of the reduced magnetic forces.

#### 2.2.5 Thermal Radiation Shield

The thermal shield, of the same design as the 6 T magnet shield, is reduced in outside diameter by about 0.95 because of the slightly smaller outside dimensions of winding and containment vessels. The overall length of shield and the size of the bore portion of the shield are the same as for the 6 T magnet.



#### 2.2.6 Low Heat Leak Supports

The supports are the same design as for the 6 T magnet but are reduced in cross-section area roughly in proportion to the cold mass weight reduction (reduction in weight of winding, containment vessels and main structure).

The smaller cross-section results in a slight reduction in heat leakage into the cold mass, but since this is a small fraction of total refrigerator load, it is not considered worthwhile to reduce refrigerator size.

#### 2.2.7 Vacuum Jacket and Warm Bore

The vacuum jacket and warm bore are of the same design as those of the 6 T magnet. The outside diameter is reduced by about 0.95, consistent with the more compact winding. Overall length and warm bore size remain identical to those of the 6 T design. The base portion of the vacuum jacket, including support pads, is slightly lighter in construction due to the lower weight of the cold mass.

#### 2.2.8 Water-Cooled Warm Bore Liner

The water-cooled warm bore liner is identical to that of the 6 T magnet.

#### 2.2.9 Vapor Cooled Electrical Leads, Internal Instrumentation, etc.

These items also are identical to those of the 6 T magnet.

#### 2.2.10 Roll-Aside System

The roll-aside system is the same design as that of the 6 T magnet but is lighter in weight because of the lower total weight of the 4 T magnet assembly.

#### 2.2.11 Cryogenic Support Equipment

The equipment is identical to that of the 6 T magnet system except for the gaseous helium storage tanks and the cooldown and warm up heat exchangers.

The gaseous helium storage tanks of the cryogenic support system, if sized for the 6 T magnet, would have some excess capacity when used with the 4 T magnet, because the latter has about 30% lower liquid helium inventory. Therefore, slightly smaller storage tanks are provided.

The size of the cooldown and warmup heat exchangers are reduced by the ratio of magnet cold mass weights.

#### 2.2.12 Vacuum Pumping Equipment; Protection/Control Equipment and Instrumentation

These items are similar to those of the 6 T magnet system.

#### 2.2.13 Power Supply and Discharge Equipment

This equipment is similar in design to that of the 6 T magnet equipment but is scaled down by approximately the ratio of the estimated inductances of the magnets (ratio =  $\frac{4.15}{9.7}$ ).

The characteristics of the power supply and discharge system for the 4 T magnet are listed in Table 2.5.

It should be noted that the maximum terminal voltage for a three minute emergency discharge is now a relatively conservative 4.3 kV as compared to 10 kV for the 6 T magnet.

### 2.3 COST ESTIMATE, 4 T MAGNET SYSTEM

A rough budgetary cost estimate for the 4 T magnet system is presented in Table 2.6.

TABLE 2.5  
4 T MAGNET SYSTEM  
POWER SUPPLY AND DISCHARGE  
SYSTEM CHARACTERISTICS

Rated current	25,000 A
Rated voltage	45 V
Current regulation	2%
Minimum charge time	
0 A to 25,000 A ( $L = 4.2$ henries)	45 min.
Minimum discharge time	
25,000 A to 0 A, normal discharge	45 min.
Minimum discharge time, emergency,	
25,000 A to 0 A	3 min.
Maximum discharge voltage	4.3 kV
Output power	
Maximum charging	1125 kW
Steady state operation	300 kW

TABLE 2.6  
SUMMARY COST ESTIMATE <sup>1,2</sup>  
ETF 4 T MAGNET SYSTEM  
CONCEPTUAL DESIGN

ACCOUNT DESCRIPTION	QUANTITY	MATERIAL COST		INST. COST	INDIR COST	CONTIN	TOTAL COST
		MJR COMP	BOA				
MAGNET SYSTEM	1	26,299	60	6,180	618	9,410	42,567
ENGINEERING SERVICES (FIELD)	-	-	-	2,653	-	530	3,183
OTHER COSTS	-	-	-	900	-	180	1,080
TOTAL ESTIMATED COSTS	-	26,299	60	9,733	618	10,120	46,830

<sup>1</sup> Costs are K\$, mid 1981.

<sup>2</sup> Does not include foundations.

### 3.0 6 TESLA MAGNET MANUFACTURABILITY STUDY

A manufacturability study and revised cost estimate were made by FBNML for the 6 T superconducting magnet system included in the MHD-ETF 200 MWe Power Plant described in the Conceptual Design Engineering Report (CDER)<sup>1</sup>.

The investigation was performed with the participation of Combustion Engineering, Inc. (CE), subcontractor to FBNML, for the express purpose of improving the manufacturability of the magnet design and providing a revised schedule and cost estimate reflecting the expertise of a heavy equipment manufacturer.

The starting point for the investigation was the ETF magnet system conceptual design prepared early in 1981 by FBNML and described in System Design Description SDD503, contained in the CDER<sup>1</sup>.

The major objectives of the investigation were to:

- a. Identify improvements in the magnet design from the manufacturability standpoint.
- b. Prepare a manufacturing plan and schedule (including on-site work) for the magnet assembly, incorporating the design improvements identified.
- c. Prepare a cost estimate for the magnet system, based on the improved design and the manufacturing plan developed.

The manufacturability study and associated cost estimating work by CE pertained only to the magnet assembly itself. The water-cooled warm bore liner, roll-aside subsystem and other accessory subsystems were not included in CE's assigned task. In arriving at a revised cost estimate for the overall magnet system, as discussed below, the revised estimated cost (by CE) for the magnet system itself was combined with the original estimated costs (by FBNML) for other components of the system as included in the overall system cost estimate breakdown<sup>2</sup> of March 13, 1981.

The magnet fabrication and assembly costs contained in this report were estimated by CE using FBNML (conceptual) drawings similar to those included in SDD503 of the CDER<sup>1</sup>, but updated to include improvements for manufacturability. Costs of material, shop labor, on-site labor, tooling, etc. were itemized for each component. In this respect, the estimate contained in this report represents a more thorough and detailed effort than the FBNML estimate contained in the CDER<sup>1</sup>, where costs were scaled from estimated costs obtained by FBNML in connection with previous investigations of larger (commercial size) magnets. However, it was not possible, with the limited time and funds provided for the present study, to prepare detailed manufacturing drawings, to make special cost-reduction studies, and to make fully detailed estimates. Any future program to advance MHD toward commercial status should therefore include further effort in magnet engineering and costing. This work should extend the existing conceptual designs into the next level of design complexity to allow the manufacturing and assembly aspects of construction to be considered in more detail with subsequent upgrade of cost estimates.

### 3.1 SUMMARY

During the initial phase of this preliminary manufacturability study, the original magnet conceptual design presented in SDD503 was reviewed and revisions were made to simplify its fabrication. These revisions are discussed in Section 3.3.3 of this report and drawings incorporating the revisions are contained in Attachment B. A manufacturing plan, schedule, and cost estimate were then prepared by CE, based on the revised design. The CE report on their work is included as Attachment A to this report.

To minimize overall costs, the manufacturing plan is based on maximizing the work done in the shop (manufacturer's plant), within the economic constraints of delivery of the components to the plant site (assumed to be Montana).

The two halves of the saddle magnet winding, each in its own helium vessel, will be completed in the shop, including vacuum-testing of the vessels. The halves, each weighing about 225 tons, will be shipped separately to the plant site where they will be joined in a special assembly fixture. Superstructure and cryostat parts will be shop fabricated and delivered in modular form for final assembly at the site.

The revised schedule, made by combining FBNML's original estimated schedule<sup>2</sup> for conductor and substructure procurement with the schedule developed by CE for fabrication and assembly of all other major parts, shows installation of the magnet on-site completed 37 months after start of contract. Allowing 6 months additional for magnet evacuation, cool-down and shake-down test (the same as in the original FBNML schedule), the total time is 43 months. This is an improvement on the original schedule<sup>2</sup> prepared by FBNML in March, 1981, which showed a total time of 45 months. Schedules are discussed in more detail in Section 3.4.

The magnet cost estimate made as a part of the manufacturing study (based on work by CE) showed the installed cost of the magnet, including on-site tools and fixtures, but not including design and analysis, special on-site costs and contingency, was \$22,669,000, compared to \$28,472,000 based on the FBNML estimate<sup>2</sup> of March, 1981.

The complete updated magnet system estimated cost, made by combining the revised magnet estimated cost with the original FBNML estimated cost for the balance of the system (roll-aside track and actuator subsystem, other support subsystems, shake-down test) and including design and analysis costs, special on-site costs and contingencies, amounts to \$49,400,000. compared to the figure of \$57,666,000 estimated in March, 1981. The revised cost estimate is discussed in more detail in Section 3.5.

### 3.2 CONCLUSIONS

- a. The magnet design utilizes construction and assembly techniques that are suitable for the larger magnets required for commercial size (500 to 1000 MWe) MHD/steam power plants.
- b. The design concept avoids the necessity for large precision machine tools. The machining operations can be performed either on subcomponents or with portable tooling.
- c. Design tolerances permit the use of as-welded structures with only a minor amount of grinding or surface preparation anticipated.
- d. The design and the manufacturing plan minimize on-site fabrication and assembly labor.
- e. The CE estimated cost of the installed magnet assembly is substantially lower than the earlier FBNML estimate contained in the CDER.<sup>1</sup> The reduction may be attributed in part to design improvements for manufacturability and to more detailed estimating procedure. However, since drawings supplied to CE were not complete in all details and since experience has shown that manufacturing cost estimates vary substantially with source, the CE estimate should not be regarded as superseding earlier estimates, but rather should be considered together with earlier estimates in determining the probable range in which the magnet cost for the ETF will lie. (See Section 3.5)

### 3.3 DISCUSSION

#### 3.3.1 Evolution of the ETF Magnet Conceptual Design

The basis for the conceptual design of the ETF superconducting magnet which is the subject of this study was the conceptual design of a larger (commercial size)

MHD magnet referred to as the "CSM" design, started by FBNML in 1979, and originally conceived as a scale-up of the CDIF superconducting magnet<sup>3</sup> design. The work on the CSM design was a part of FBNML's overall MHD magnet technology development program, which included the preparation and evaluation of several reference (conceptual) design commercial-size MHD magnets. Although evaluations are not yet complete, the CSM design appears to be the most suitable for early commercial scale and ETF size magnets.

The original CSM design concept incorporated a rectangular saddle coil configuration and pancake-type windings in which individual conductors were supported in grooves in an insulating substructure. The conductor was thus kept free of accumulated magnetic loads, and the potential magnitude of mechanical disturbances at conductor surfaces was minimized. The conductor was bath-cooled and large passages were provided in the substructure to accommodate the liquid helium coolant. The superstructure and helium vessels were of stainless steel. All these features were common with the CDIF magnet design and were believed to contribute both to the reliable operation and ease of manufacture. (These features were ultimately retained in the ETF magnet design.)

As the CSM design progressed, it departed from the CDIF in several respects because of the difference in scale. These departures included the following:

- a. Circular cable-type conductor was used in place of the rectangular built-up conductor (copper bar type) employed in the CDIF magnet.
- b. The substructure was made up of a large number of small molded glass-reinforced pieces instead of the continuous G-10 plates with machined grooves as used in the CDIF magnet.
- c. The helium containment vessel was closely fitted around the windings, with superstructure located outside the vessel in the vacuum space. This contrasted with the CDIF magnet design in which the superstructure was fitted directly on the windings and helium vessel outer walls surrounded the superstructure.

All three CSM features listed above were introduced mainly to facilitate manufacturing and to reduce costs.

Drawings were made of the CSM winding, containment vessel, superstructure and general assembly. They show the two halves of the winding enclosed in a single containment vessel, and an all-welded superstructure closely integrated with the containment vessel (in an effort to reduce amount of material). With this design, it was assumed that the coil container would be fabricated in part on-site, the coils would be wound into the container on-site, and a substantial amount of on-site welding would be required to close the vessel and complete the superstructure.



The design was reviewed for manufacturability with engineers and manufacturing representatives of Pittsburgh Des Moines Steel Co. As a result, it was decided to change the design (for improved manufacturability) such that a major portion of the superstructure was in the form of I-beams and threaded tie rods, which could be shop-manufactured and then assembled around the containment vessel with minimum on-site labor, thereby reducing cost.

The ETF magnet design, as described in the CDER<sup>1</sup> (SDD503), is a scaled-down version of this CSM design. Subsequent revisions are described in Section 3.3.3.

### 3.3.2 Alternative Concepts

Alternative design concepts which may be considered for the ETF magnet include the square bore concept<sup>4</sup> developed by Magnetic Corporation of America in 1977, the circular-bore "Cask" concept<sup>4</sup> developed by General Dynamics under FBNML sponsorship, the circular-bore, cylindrical-layer concept represented by the CFFF magnet<sup>5</sup> built at Argonne National Laboratory, the 1978 Avco Everett Research Laboratory ETF design<sup>6</sup>, and the roll-apart concept<sup>7</sup> proposed by Avco Everett Research Laboratory in 1981.

The evaluation of these concepts, together with the CSM concept and others developed at FBNML, is a continuing activity and has not yet reached the point where any one design can be finally identified as most suitable.

A preliminary study of magnet/power-train interfacing,<sup>8</sup> carried out by FBNML early in 1981, with assistance from Avco and MEPPSCO, indicated that the rectangular bore is quite suitable for channel installation and generally permits better utilization of the high magnetic field volume produced by the magnet coils than does the circular bore. However, the detailed characteristics of applications and power train designs will, of course, influence final selection of bore shape in particular cases.

In choosing the rectangular bore and rectangular saddle coil concept (non-roll-apart) for presentation in the CDER<sup>1</sup>, FBNML was influenced by the following factors:

- a. The rectangular bore, rectangular saddle coil concept appears to be generally superior from the standpoint of magnetic volume utilization.
- b. In our opinion, the rectangular saddle coil concept as represented by the ETF magnet design described herein is easy to manufacture and is favorable from a cost standpoint, as compared to other designs considered to date.
- c. We expect that designs without substructure will present problems relative to the accumulation of local em loads and transmission of them to the superstructure, when scaled to commercial size; therefore, a substructure is considered essential.

- d. The roll-apart concept has not been tried in a superconducting magnet and has not yet been investigated in depth. It is therefore considered too developmental for the ETF.

### 3.3.3 Revisions to ETF Magnet Design to Improve Manufacturability

During the review of the ETF magnet design by CE, starting early in 1981, revisions were made to upgrade the design and further facilitate manufacturing. These changes included the following:

- a. The winding containment vessel was divided into two separate vessels, one for each winding half. Because of this change, windings can now be installed in the shop for cost saving. (The revised design provides that the two vessels, with windings installed, will be shipped separately from shop to site, where they will be joined and liquid helium cross-connections, vent stack, etc. added. Shipping both halves together as a unit would be impractical because of the very large overall dimensions).
- b. Lifting lugs were added to large components to facilitate assembly.
- c. Main support struts were canted to provide for a wider support base.
- d. Winding pattern was revised so that fewer special substructure pieces are required.
- e. Winding exit-end substructure crossovers and corresponding container parts were enlarged to provide adequate room for power-leads.
- f. Exit-end stack was eliminated, to reduce cost.
- g. Inlet-end stack and liquid helium reservoir were enlarged to provide larger helium reserve and facilitate assembly.
- h. Greater clearance was provided between vacuum jacket outer shell and cold parts to facilitate assembly. (Jacket diameter increased).
- i. Vacuum jacket heads were changed to flat plates instead of plates with curved (radiused) outer edges, to reduce cost.
- j. Vacuum jacket side covers were eliminated to reduce cost. (The revised design provides for entire top half of jacket shell to be a separate module, removable by grinding welds.)

### 3.3.4 Drawings

A set of 15 drawings, included as Attachment B in this report, show the ETF 6 T magnet components as revised during this study.

Because of limited time and funding available, it was not possible to prepare revised general assembly drawings, outline drawings, etc.

The overall diameter of the magnet, as revised, is 30' (compared to 27' 6" originally). The overall length remains unchanged.

### 3.4 REVISED SCHEDULE, 6 T MAGNET SYSTEM

The critical path schedule for magnet system manufacture and installation, based on the CE estimate of time required for magnet major parts fabrication, is shown in Fig. 3.1. The total time through shake-down test is 43 months, which is shorter by 2 months than the estimated schedule<sup>2</sup> prepared by FBNML in March, 1981.

It should be noted that the CE schedule contained in their Manufacturability Report, Attachment A, allows an extra 3 month period at the start for design (manufacturing drawings) of the conductor and substructure, which was not included in the FBNML schedule of March, 1981. With this extra time included, the total critical path time amounts to 45 months (the same as in the original FBNML schedule<sup>2</sup>) and there is a waiting period of 2 months in the coil container schedule. It is reasonable to assume that a major part of conductor and substructure manufacturing drawing work can be done during the design and analysis phase of the project. Based on this assumption, 2 months can be deducted from the overall schedule and the total time shortened to 43 months, as shown on the revised schedule, Figure 3.1.

### 3.5 REVISED COST ESTIMATE, 6 T MAGNET SYSTEM

The revised cost estimate for the magnet system, incorporating the new CE estimate for magnet fabrication and assembly but retaining substantially the same estimates for other elements of the system (accessories, roll-aside equipment, etc.) as appeared in the original FBNML estimate<sup>2</sup>, is presented in Table 3.1, Summary Cost Estimate and Table 3.2, Cost Estimate Breakdown.

It should be noted that the CE estimate for the magnet used the same costs of conductor, substructure and internal instrumentation as used in the original FBNML estimate<sup>2</sup>. Costs of coil containers, structure, cryostat, assembly, etc. were new estimates made directly by CE using FBNML revised drawings.

The CE estimates showed reductions in (shop) manufacturing cost of about 500 k\$, in on-site tooling of about 1500 k\$ and in on-site installation of about 3500 k\$ (not including design and analysis, special on-site costs and contingency).

FIGURE 3.1  
CRITICAL PATH SCHEDULE  
ETF 6 T MAGNET SYSTEM (REVISED)




TABLE 3.1  
SUMMARY COST ESTIMATE<sup>1,2</sup>  
ETF 6 T MAGNET SYSTEM  
CONCEPTUAL DESIGN (REVISED)

ACCT. NO	ACCOUNT DESCRIPTION	QUANTITY	MATERIAL COST		INST. COST	INDIR COST	CONTIN	TOTAL COST
			MJF COMP	BOA				
317.3	MAGNET SYSTEM	1	31,383	80	2,975	298	9,984	44,720
	ENGINEERING SERVICES (FIELD)	-	-	-	2,921	-	584	3,505
	OTHER COSTS	-	-	-	985	-	197	1,182
	TOTAL ESTIMATED COSTS	-	31,383	80	6,881	298	10,765	49,407

ORIGINAL PAGE 13  
OF POOR QUALITY

<sup>1</sup>This cost estimate does not include foundations.

<sup>2</sup>Costs are K\$, 1981

TABLE 3.2  
COST ESTIMATE BREAKDOWN<sup>1,7</sup>  
ETF 6 T MAGNET SYSTEM - CONCEPTUAL DESIGN (REVISED)

ACCT. NO.	ACCOUNT DESCRIPTION	MAN.	DESIGN & ANAL.	MAT'L & MFG.	SHOP ENG'G	PACK & SHIP	MATERIAL KIT COMP	COST <sup>2</sup> DOA	INST COST	INDIR COST	ENG'G SERV. 8	OTHER COST	CONTIN.	TOTAL COST
317.3.1	Magnet assembly													
317.3.1.1	On-site tools						356		0					
.2	Roll-aside track						621		150					
.3	Wind. contain vessels <sup>3</sup>						15,521		987					
.4	Main structure						5,118		Incl. above inc. below					
.5	Cold mass supp. struts						717		120					
.6	Therm. rad. shield						591		738					
.7	Vacuum vessel						3,676		80					
.8	Warm bore liner						839		2,075	208	2,520	850	8,917	38,639
	Total magnet assembly						27,439							
317.3.2	Support subsystems													
317.3.2.1	Hydro. actuator sys.						128		30					
.2	Cryogenic supp. system						1,536		250					
.3	Power supply & dis. sys.						1,152		150					
.4	Main vacuum pump sys.						256		70					
.5	Utility boom, contr., misc.						640		100					
	Total support system						3,712		600	60	550	118	874	5,246
317.3.3	Magnet shakedown test						232	80	300	30	51	17	193	835
Total							31,383	80	2,975	298			9,984	44,720
	Engineering Services										2,921		584	3,505
	Other cost											985	197	1,182
317.3	TOTAL												10,765	49,407

- 1 This estimate does not include foundations.
- 2 Material cost is FOB site.
- 3 This item includes conductor, coil winding (in shop) and shop assembly.
- 4 Includes 100 K\$ eng'g. test supervision and analysis.
- 5 Includes liquid nitrogen and liquid helium.
- 6 On-site technician labor cost.
- 7 Costs are K\$ mid 1981.
- 8 Field engineering

These substantial reductions can be attributed in part to design improvements for manufacturability and to the fact that the CE estimates were made by experienced manufacturing people based on ETF magnet component drawings, whereas the earlier estimates were made largely by scaling from budgetary estimates of larger magnet costs and may have been overly conservative. However, since drawings supplied to CE by FBNML were not complete in all details and since it is known that estimates made by different manufacturers tend to vary considerably, the estimates discussed in this report should be considered preliminary and subject to further revision when more detailed design and estimating is accomplished. It is our recommendation that until more comprehensive estimates are made, the ETF magnet system budgetary cost be taken as in the range from  $\$50 \times 10^6$  to  $\$60 \times 10^6$  (median  $\$55 \times 10^6$ ).

### 3.6 REVISED WEIGHT ESTIMATE, 6 T MAGNET SYSTEM

The estimated weight of the magnet assembly based on the updated design and more detailed estimating procedure used in this study is about 2,200,000 lb., as compared to 2,000,000 lb. listed in SDD501. A part of the increase results from redesign of the vacuum vessel base to provide more conservative stiffness and structural strength. The balance of the increase is attributable to a more detailed estimating procedure.

## References

1. Conceptual Design Engineering Report (CDER) MHD-ETF 200 MWe Power Plant, September, 1981, prepared by Gilbert/Commonwealth, Engineers/Consultants for National Aeronautics and Space Administration, Lewis Research Center and U. S. Department of Energy, Fossil Energy, Office of Magnetohydrodynamics DOE/NASA/0224-1 NASA CR 165452, Volumes I through V.
2. Letter from A. M. Hatch (FBNML) to J. A. Burkhart (NASA LeRC) dated March 13, 1981 with the following enclosures:  
  
    Summary Cost Estimate, ETF Magnet System Rev. 3/13/81  
  
    Cost Estimate Breakdown, ETF Magnet System Rev. 3/13/81  
  
    Schedule - Manufacturing and Installation, MHD-ETF 200 MWe Power Plant Magnet System (2 sheets) 3/2/81
3. Conference Paper, "Status of the CDIF Superconducting Magnet", R. L. Rhodenizer, et al, General Electric Co., Proceedings of the MHD Magnet Design Conference, MIT, Cambridge, MA, March 1980.
4. Final Technical Report, "Cask Commercial Demo Plant MHD Superconducting Magnet System - Conceptual Design . . . .", S. L. Ackerman, et al, prepared for MIT/FBNML by General Dynamics Convair Division, December 1979.
5. Conference Paper, "The Fabrication Experiences and the Performance Test of the Coal-Fired Flow Facility Superconducting Dipole Magnet", S. T. Wang, et al, Argonne National Laboratory, 19th Symposium, Engineering Aspects of MHD, the University of Tennessee Space Institute, Tullahoma, TN, June 1981.
6. Report, "Design and Cost for the Superconducting Magnet for the ETF MHD Generator", J. L. Zar, AVCO Everett Research Laboratory, Inc., April 1979, prepared for MIT/FBNML.
7. Private communication, J. L. Zar, AVCO Everett Research Laboratory, Inc. to A. M. Hatch, MIT/FBNML dated May 27, 1981.
8. Conference Paper, "Magnet-Flow Train Interface Considerations", P. G. Marston, A. M. Dawson, A. M. Hatch, MIT/FBNML; T. R. Brogan, MEPPSCO, Inc., 19th Symposium, Engineering Aspects of MHD, the University of Tennessee Space Institute, Tullahoma, TN, June 1981.
9. Letter from J. M. Tarrh, MIT/FBNML to J. A. Burkhart, NASA LeRC dated April 6, 1981 confirming agreement on definition of tasks under NASA LeRC Grant NAG-3-100.
10. Final Report, "Design of Superconducting Magnets for Magnetohydrodynamics (MHD) Applications", R. J. Thome, et al, prepared for DOE (for early ERDA) by Magnetic Corporation of America, June 1977.



**ATTACHMENT A**

**Manufacturability Report**

**MHD-ETF 200 MWe Power Plant Magnet System**

**Conceptual Design**

**prepared for**

**Massachusetts Institute of Technology  
Francis Bitter National Magnet Laboratory**

**by**

**Combustion Engineering, Inc.**

**September, 1981**

**ORIGINAL PAGE IS  
OF POOR QUALITY**

## Manufacturability Report

### MHD-ETF 200 MWe Power Plant Magnet System

#### Conceptual Design

#### 1.0 INTRODUCTION

The manufacturability of the magnet and vacuum vessel of the MHD-ETF 200 MWe Power Plant Magnet System has been investigated by Combustion Engineering, Inc. The magnet concept was designed by the Massachusetts Institute of Technology, Francis Bitter National Magnet Laboratory (MIT-FBNML).

The magnet assembly included in this report consists of two saddle coils in their helium vessels, the thermal shields surrounding the superconducting coils, and the vacuum vessel in which the magnets are located. MIT-FBNML retained responsibility for estimating the design and analysis, the substructure, conductor, instrumentation, structural supports, the supporting cryogenic systems, and the system for moving the magnet assembly to one side for maintenance. The warm bore liner, electrodes, etc., are not included. The components are as described in the Preliminary System Design Description, SDD-503, Magnet System for Magnetohydrodynamics Engineering Test Facility Conceptual Design-200 MWe Power Plant.

The magnet system design accommodates construction and assembly techniques that are suitable to the larger magnet systems required for a commercial size (1000 MWe) MHD/steam power plant. (The ETF size permits completion of the magnet halves in the shop with barge and truck delivery to Butte, Montana.) The design concept avoids the necessity for large precision machine tools. The machining operations can be performed either on subcomponents, or with portable tooling. The design tolerances permit the using of as-welded structures with only a minor amount of grinding anticipated.

The general manufacturing plan is based on maximizing the work done in the shop within the economic constraints of delivery of the components to Butte, Montana. The two saddle magnet coils will be completed in the shop, including vacuum testing of the helium vessels with temporary closures. The superstructure parts (beams and tie rods) will be completed and delivered to the site for assembly. The thermal shields and vacuum vessel will be shop fabricated and delivered for final assembly at the site. The detailed description of the elements of this plan follow.

### 1.1 Materials

The materials selected by MIT-FBIML are 316LN stainless steels for the cold mass structures Type 6061 aluminum alloy for the thermal shields and 304L stainless steel for the vacuum vessel. The surfaces of materials are not polished for vacuum service. Grain size determination and Charpy impact testing have not been required. Fracture toughness testing of the 316LN material is required in certain critical areas to be defined later. (The mill has declined to quote on performing testing at 4.2K.) Physical properties are not required at 4.2K, but will be determined to enable selection of best materials for critical areas of design. The plates are to be ultrasonically tested. Based on the above requirements the type 316LN plate was quoted at \$2.50 per pound, the type 304L plate at \$1.77, and aluminum 6061 alloy at \$1.77 per pound. The cost of testing at 4.2K has not been included in these quotations.

### 1.2 Magnet Coil Cases (Helium Vessels)


The magnets are encased in Type 316LN stainless steel structures that also serve as liquid helium vessels. The two magnet cases are made as left- and right-hand parts to accommodate the helium piping upon assembly. The two cases can be fabricated in parallel operations, but shipping considerations and field assembly place both halves on the critical path. Shop fabrication is based on the following subcomponents.

**ORIGINAL PAGE IS  
OF POOR QUALITY**

**ORIGINAL PAGE IS  
OF POOR QUALITY**


- 2 - Outlet Crossover Subassemblies
- 2 - Inlet Crossover Subassemblies
- 4 - Base Plate Subassemblies
- 2 - Inner Side Plate Subassemblies
- 2 - Outer Side Plate Subassemblies
- 2 - Sets of Cover Plates

### CROSSOVER SUBASSEMBLIES




The four crossover subassemblies are on the critical path, with the larger (outlet ends) units requiring the greater effort. The crossover subassemblies support the conductor and substructure as it passes around the gas flow ducts. The forces are large, requiring short spans between supporting gussets. The three-inch thick base plate is extended beyond the conductor box to permit attachment of supports incorporated into the superstructure. The resulting dimensions (151" x 253" and 136" x 230") exceed the dimensions of plate obtainable from the mill, requiring two pieces for each base plate. Before the two pieces are joined by butt welding, they are formed to a 60 degree templet and the excess material removed by burning. The support pieces and gussets are also cut to dimensions and two pieces are formed to follow the outer edge of the crossover bends. The four crossovers require 222,600 pounds of material to be ordered, with 135,670 pounds in the completed parts. There are 184 feet of 2-inch welds and 35 feet of 3-inch welds, requiring over 1370 pounds of weld wire.

### BASEPLATE SUBASSEMBLIES



The baseplate subassemblies space the crossovers at the proper distance. These four simple subassemblies require 68,300 pounds of type 316LN stainless steel to be ordered. Due to the tapered supports, only 48,375 pounds remain in the finished parts. The tapered support welded to the base plate do not require full penetration welds. The 576 feet of welds require only 512 pounds of weld wire. These subassemblies are joined between inlet and outlet crossover subassemblies using full penetration welds. This assembly operation establishes the overall dimensions and alignment of each magnet half.

### SIDEPLATE SUBASSEMBLIES




The inner and outer sideplate assemblies are made from six pieces. The long straight sides are 2" plate. The transition plate and crossover pieces are 3" plate. The side plates accommodate the widening

**ORIGINAL PAGE IS  
OF POOR QUALITY**


of the magnet halves from the inlet to outlet ends. The material ordered weighs 254,409 pounds. The finished pieces weigh 235,040 pounds. The required weld length is 190 feet. The transition plates are machined for required fit-up, with slots for the cross coil superstructure beams, and with holes for helium, electrical leads, and instrumentation access. The inner assembly has a "filler plate" welded at each end. The filler plate distributes the end load from the crossover windings into the side plates. The fit-up and assembly of these parts to the structure forms the open box into which the substructure and conductor will be placed.

COVER PLATES




The preparation of two sets of cover plates is not on the critical path, as they are not required until after the winding operations are complete. The cover plates cannot be prewelded, as the configuration of the crossovers creates an "overhand" for an assembled cover plate. The cover plate parts are relatively simple, consisting of two long pieces with formed ends to fit the sixty degree bend at the crossover, and two flat plates snapped to the inlet and outlet crossovers, with allowances of excess material for removal during final fit-up.

SUBASSEMBLY



During assembly of the side plates to the structure, the squareness and straightness of the space for the conductors will be continuously verified. The next critical path operations are the assembly of substructure and winding of the conductor. A fixture will be made to support two reels of conductor above a half magnet. The conductor box will be prepared by cementing ground plane insulation to the base plate and sides. In this operation, any unevenness of the surfaces will be corrected by filling, or grinding of excess material.

WINDING OF CONTRACTOR




The winding of conductor is preceded by placement of two perforated tubing loops into the substructure grooves. The stainless steel tubing is used to distribute helium gases during controlled cooling and heating of the cold mass from and to room temperature. The introduction of these tubing loops and of the conductor requires the outlet crossover to be wider and deeper than the inlet crossover and special pieces of substructure to be used. The conductor lead is fed out of the channel into the helium "stack" space where it is coiled for shipment of the magnet to the site. With the tubing loops and conductor lead in place, the remaining substructure for the first layer of conductor is installed. In this first layer, only four turns are placed prior to a splice between this Grade A conductor and the Grade B conductor. The splices used in the magnet are mechanical assemblies compressing the ends of each grade in a copper block.

The winding of the twenty turns of Grade B conductor proceeds to complete the first layer. The first layer is completed with the conductor at the outside of the outlet crossover. At this time the second layer of substructure is placed and bolted to the first layer pieces. In-process tests are conducted. The winding of the second layer proceeds from the outside toward the inside of the coil. When seventeen turns of Grade B conductor are placed, a splice to Grade A conductor is made. Succeeding layer pairs are placed in a similar sequence. The location of the splice between conductor grades steps toward the outside of the coil, with the last eight layers being wound with only Grade A conductor. The last layer is wound from the outside to the inside of the coil. Special substructure blocks are added to carry the conductor lead across the top of the bundle. The lead end is fed through the bushing in the case and coiled for storage during shipment to the site. As the conductor is wound into the substructure, the internal instrumentation is applied as required. The instrument leads are carried out through bushings and coiled for shipment.



CLOSING COIL CONTAINER



When all layers of conductor and all internal instrumentation have been completed, the ground insulation panels are placed atop the conductors and substructure. Although each layer of substructure is bolted to the next lower layer, the entire bundle will be spring loaded to preload the assembly when the cover plates are applied. The springs are placed, and the cover plates fitted. A group of compression jacks are used to preload the conductor bundle through the cover plates and the plates are tack welded. When all plates satisfy the requirements, welding is completed, including the butt joints between cover plate pieces.

At this stage, temporary covers are welded into the helium openings, and the vessel is vacuum tested. Final shop inspection is made, and any of the superstructure beams that will not interfere with shipment are added. Both coil halves are packaged for shipment and, with other components, will be shipped by barge to the west coast.


1.3 Magnet Superstructure

The design of the superstructure consists of beams and tie bolts to equilibrate the repulsive magnetic loads, with intercoil beams and ties welded to the crossovers to transfer those loads into the helium vessel. Due to the expansion of the gas through the magnet, the dimensions of the beams and tie rods increase continuously from the inlet to outlet ends. Furthermore, due to this taper, only one flange on each beam can be square to the

web. The 56 beams are made from 257,500 pounds of type 316LN stainless steel plate and 57,000 pounds of Type 316LN stainless steel pipe. The 56 studs weigh from 3005 pounds to 3350 pounds each. The 112 nut and washer sets weigh 175 pounds each. There is 1390 feet of welding required to make the beams, 980 feet of which can be machine welded. The miscellaneous superstructure associated with the crossover weighs over 63,750 pounds. Except for the beam across the sixty-degree bend line of the crossovers, all the superstructure is added when the two halves are joined at the site.


#### 1.4 Thermal Shield

The thermal shield intercepts heat radiated through the space from the vacuum vessel walls toward the liquid helium cooled magnet and structure. The shield consists of 3/8 inch thick aluminum sheets with liquid nitrogen filled tubing attached as needed. The sheeting is surrounded on both sides by mirrored mylar film insulation layers.




The inner thermal shield is a truncated pyramid that fits between the warm bore of the vacuum vessel and the helium vessels of the magnet. It is made of five short sections that assemble with tongue and groove joints. Each of the sections has cooling tubing attached. The nitrogen distribution and collection headers are installed after assembly in the field. Each of the sections is attached to the warm bore of the vacuum vessel before this assembly is inserted into the magnet. The mirrored mylar insulation is also positioned during the site assembly of the vacuum vessel.

**ORIGINAL PAGE IS  
OF POOR QUALITY**



The outer thermal shield consists of 32 quarter rings. These pieces are joined by insulated bolted flanges. The stainless steel nitrogen cooling lines are not electrically insulated at these joints. The lines are joined after the cylinder is assembled. The cylinder is 350 inches (29 ft 2 in) in diameter and fifty-two and one-half feet long.




The two heads are each made in four pieces again using electrically insulated flange joints. The heads are attached to the outer thermal shield. The assembly is hung from the lower half of the vacuum vessel. A pair of "V" struts attach the two center rings to the outershell and act to center the assembly during cool-down and heat-up. The remaining rings are simply supported to permit differential expansion.

## 1.5 Vacuum Vessel

The vacuum vessel is designed to operate at room temperature and to maintain a vacuum of  $10^{-8}$  torr without the cryogenic temperature components being in service. The vessel is 383.5 inch diameter over the stiffener rings and 56 feet long. The vessel consists of truncated trapezoidal-shaped "warm bore", with flat plate heads and a ring reinforced cylinder. In order to maximize shop fabrication to accommodate the assembly sequence and to meet material handling problems, the vacuum vessel is made in the following sections:


1 Warm Bore	90" x 116" x 660"
2 Heads	2 - 90" x 307" subassemblies
	1 - 146" x 340" subassembly
	2 - 73" x 279" subassemblies
	1 - 171" x 340" subassembly
1 Outlet End Support Box	120" x 340" x 155"
1 Inlet End Support Box	120" x 340" x 135"
12 Cylindrical Panels	4 - 128" x 624" panels
	4 - 128" x 348" panels
	4 - 107" x 138" panels

### 1.5.1 Warm Bore




The warm bore is a truncated trapezoid some 55 feet long with ends of 120" x 145" tapering to 67" x 82". The thickness of the warm bore varies from 3" at outlet to 2" at inlet. Over 180,700 pounds of material must be ordered with the finished weight being 151,282 pounds.

1.5.2 Vacuum Vessel Heads




Each of the heads will be divided into three pieces for shipment to the field. Two sides of the head will be shipped as flat plates prepared for field welding. The center section will be a subassembly of the top and bottom plates joined to the transition sections. Of the 189,600 pounds of type 304L stainless steel purchased, 154,150 pounds remain in the finished heads.

1.5.3 Outlet Support Box



The support box structure at the outlet end of the vessel contains the pads for the main structural supports and two pads for carrying the axial and lateral seismic loads. The support box rests upon the cross beams on which the entire magnet is rolled aside some 34 feet to perform maintenance on the warm bore liner. The weldment is shop fabricated from 1-1/2" to 3" thick plate.


1.5.4 Inlet Support Box



At the inlet end, the support system accommodates the shortening of the cold mass during cooldown. Therefore, only the two main structural support columns and one lateral load support are included. The inlet box sub-assembly is shorter than the outlet box, as there are no axial load columns involved. A portion of cylindrical shell is attached to make up the dimension to the head flange. The inlet box rests upon a set of cross beams as does the outlet box. The weldment is shop fabricated.

1.5.5 Cylindrical Panels

There are twelve panels in the vessel, as required to accommodate shipping restrictions and the desired assembly sequence. These panels are prefabricated in the shop and shipped to the site. Four long panels are joined to make a half cylinder for the top of the vessel. The remaining panels are joined with the support boxes to make the lower half of the vessel.



Material procurement affects the fabrication plans for the shell. The rolling of the 3/4 inch plate requires extra length on each piece to secure the curvature to the joint.

Transportation of the pieces from the mill to the shop sets a width limitation. Shipment of the panels to the site requires dividing the cylinder into eight long, curved panels.

The materials purchased for the shell weigh 182,343 pounds; for the flanges, 79,539 pounds. The width of the panels shipped is 147".

#### 1.6 Cryogenic Stacks and Piping

The helium and nitrogen connections within the vacuum boundary will be pre-fabricated in the shop. The piping and fittings will be joined, but the subassemblies will be selected to provide materials for final fit-up at the site.

#### 1.7 Shipment

Since the weight and size of the saddle coils exceeds normal rail limitations, the delivery of the ETF magnet by barge and truck has been proposed. The necessary detailed investigation of clearances and bridge weight limits has not been made for this study. The experience of C-E's traffic department in delivery of nuclear reactor components to remote sites is the basis for the route selection and delivery estimate included. The route involves shipment of all components from the shop on one barge to a west coast port. From that point, the components would be transported to the site by special trucks. The necessary work to relocate overhead lines and reinforce culverts and bridges as required has been included in the packing and shipping estimate of 1,734,000.

#### 1.8 Site Assembly

Most of the site work consist of assembling the parts made in the shop. Parallel operations are permitted on the vacuum vessel assembly, the magnets and superstructure and the thermal shields. The critical path involves the magnet halves, superstructure, and assembly of all components. The C-E study did not include completion of the vacuum

system, cryogenic system, power system, controls for the magnet, or the site testing and checkout.

In order to insert the warm bore into the assembly, a fixture has to be used. This fixture consists of a beam around which the components are assembled. The fixture must be over twice the length of the assembly, in order to have its supports outboard of the assembly with the warm bore ready for installation. A 60 inch square beam of 1" and 2" plates with a length of 120 feet was conceived. During insertion of the warm bore (181,000 pounds) the beam will deflect about 3-1/4 inches. For economy, this beam was estimated based on carbon steel construction. Therefore it must be stored well away from the magnet during operations.

Each magnet half will be attached to ring supports on each end. The ring supports will permit orientation of the magnet for down hand welding of most joints. Two welding crews and one beam assembly crew will work on the assembly simultaneously for some eight months.

During this time, the vacuum vessel and thermal shield subassemblies will be joined to make up the vessel into lower and upper halves. The mirrored mylar insulation will be attached to the inner thermal shield assembly. These operations are not on the critical path.

When the magnet assembly is completed, with the helium piping and the helium and nitrogen stacks attached, the assembly on the fixture will be raised and the lower half of the vacuum vessel moved on its tracks beneath the magnets. The magnet support system will be attached as the magnet is lowered into the vessel. The outer thermal shield will be attached to the assembly, with the superinsulation in place. The upper vessel shell will then be attached. Lowering of the upper shell onto the assembly is critical. The cryogenic connections are made through the vessel head, and the final movement of the head requires precise positioning. At this time, the magnet is released from the fixture. The support of the fixture is changed to permit one vessel head to be fitted and welded to the vessel shell. The fixture supports are again changed permitting the warm bore and other closure head to be placed



thereon. This assembly is supported on the fixture at each end by adjustable, rolling supports. The assembly is carefully inserted through the magnet, and joined to the opposite head. The final closure of the vacuum vessel then proceeds.

After the conductor and instrumentation leads are connected to the external wiring, the cryogen systems are connected. The vacuum vessel is tested for leaks, and brought to specified vacuum specifications. The nitrogen system is retested, and cooldown of the cold mass begun. These tests are followed by testing of the magnet and checkout of all systems.

## 2.0 Cost Estimation

Table 2-1 provides a tabulation of the estimated costs for the MHD ETF magnet. The costs for superconductor, substructure instrument and cold mass supports were estimated by MIT-FBNML. The total magnet costs of \$22,459,000 are in 1981 dollars without any contingencies having been added. It is, of course, for a conceptual design that has not included many of the details required for a final design. This estimate is believed to provide an accurate base figure for requesting a project budget.

## 3.0 Critical Path Schedule

Figure 3-1 provides the preliminary critical path schedule for the MHD ETF magnet concept. The schedule assumes that detailed design and analysis of the magnet system has been completed prior to award of a contract to fabricate. Three months are provided to prepare shop drawings of the components sufficient for material procurement. The conductor material procurement times for conductor were provided by MIT-FBNML. Those for stainless steel are based on quotations from G. O. Carlson reflecting current mill capacity. The fabrication spans were a minimum in this estimate, as is proper for critical path determinations. The delivery of conductor became the critical path, followed by winding of the coils, closing the cases, and packing for shipment. Both coils are wound simultaneously, requiring two winding fixtures.

Table Z-1

## COMPILATION OF ESTIMATED COSTS FOR MHD ETE MAGNET

ENTRY ITEMS	Weight Installed, K pounds	Weight Purchased, K pounds	Special Tools, K\$	Material Costs K\$	Shop Labor Costs K\$	Shop Labor Shop Eng'rs Costs K\$	Total S. D. C. K\$	Mfg. Costs including G&A plus profit	Pack & Ship Costs K\$	At-Site Costs K\$	On-Site Tooling Costs K\$	Assy. & Int. Costs K\$	Total Costs K\$
1 Superconductor	226	262		6500	included in 5	in 5	6500	7507					
2 Substructure	180	200		950	included in 5	in 5	950	1097					
3 Instrumentation, Int. Piping				100	included in 5	in 5	100	115					
4 Cool Container Weldment	900	630		1574	192	66	1832	2116					
5 Winding and Assembly			124		343	117	584	675					
6 Subtotal - Magnet Coils	906	1092	124	9124	535	183	9966	11510	725	12225	235	987	13447
7 Superstructure	526	530		2048	862	295	3205	3703	415	4118		in 6	4118
8 Thermal Rad. Shields/Stacks	76	82		180	92	32	312	360	58	418	45	120	583
9 Cold Mass Supports	22	22		485	-	-	485	560	6	566		in 11	566
10 Vacuum Vessel	669	814		1656	164	125	2145	2477	530	3007		396	3403
11 Final Assy. & Installation												342	342
12 TOTAL	1293	1448		4377	1318	452	6147	7100	1009	8109	45	858	9012
13 TOTAL MAGNET	2199	2540		13501	1853	635	16113	18610	1734	20334	280	1845	22459
14 Tracks and Rollers													
15 Hydraulic Actuators													
16 Utility Room													
17 Subtotal - Roll Aside Sys.									1538				
18 Warm Bore Liner	30								865			80	945
19 Cryogenic Support Systems													
20 Power Supply & Dist. Sys.													
21 Main Vacuum Pump Sys.													
22 Subtotal - Accessories									3238				
23 Instrumentation & Controls													
24 Shutdown Tests													
25 TOTAL													
26 Engineering Services													
27 Other, Total													
28 GRAND TOTAL													


ORIGINAL PAGE IS  
OF POOR QUALITY

The delivery of all components by barge causes a "bottleneck". Site work cannot proceed, except on the assembly fixtures, until all components are delivered. At the site, the assembly of the cold mass is the critical patch. The vacuum vessel and thermal shield subassembly work can easily be performed during the eight months required to assemble the cold mass. Assembly of the other components and testing requires the remaining seven months.

Forty months from order placement appears to be an attainable schedule for the design concept studied.

ORIGINAL PAGE IS  
OF POOR QUALITY

FIGURE 3-1  
PRELIMINARY SCHEDULE  
MHD ETF MAGNET  
CRITICAL PATH ONLY



## ATTACHMENT B

### Drawings of ETF 6 T Magnet

#### Components (Revised)

The following drawings show magnet components that were revised to upgrade the design and improve manufacturability. The manufacturing schedule and cost estimate included in this report were based on the revised design as shown in these drawings.

J-4700-600	Sht. 1-4	Vacuum Jacket Base & Cold Mass Ass'y.
J-4700-601	Sht. 1-3	Cold Mass Assembly
J-4700-602	Sht. 1-2	Coil Container Assembly
J-4700-603	Sht. 1-2	Coil Container & Insulation Assembly
J-4700-604	Sht. 1-2	Coil Container Weldment
D-4700-605	————	Layer #2 Winding Detail
D-4700-606	————	Layer #3 Winding Detail
D-4700-607	————	Layer #26 Winding Detail
J-4700-610	Sht. 1-3	Outer Thermal Shield
J-4700-614	Sht. 1-3	Inner Thermal Shield
J-4700-615	Sht. 1-4	Vacuum Jacket Assembly
J-4700-616	Sht. 1-2	Service Stack Assembly
E-4700-300	————	Substructure Detail, Straight
E-4700-301	————	Substructure Detail, Corner
E-4700-302	————	Substructure Detail, Curved


ITEM NO	PART NO	DESCRIPTION	MAT'L QTY	WEIGHT
1	2-4700-600	COLD MASS ASSY	1	
2		VACUUM SOCKET BASE WELDMENT	1	
3		THEP HALL SHIELD LOWER HALF	1	
4		VERTICAL SUPPORT STRUT ASS	4	
5		TRANSVERSE SUPPORT STRUT ASSY	2	
6		HORIZONTAL SUPPORT STRUT ASSY	2	
7		HOLD-DOWN BRACKET	4	
8		ROLLER UNIT (MILLMAN 72)	4	
9		HYDRAULIC CYLINDER	4	
10		TRACK ASSY	2	
11		BOLT 3/4 X 10 L6	40	
12		NUT-HEX 3/4	40	
13		WASHER STD	40	
14		LOCK WASHER STD	40	

ORIGINAL PAGE 19  
OF POOR QUALITY

REF DES 2-4700-600 DWT 2, 3, 2, 4




REV	DESCRIPTION	BY	DATE
TITLE: PROPERTY OF THE PLANT WAREHOUSE SYSTEM			
VACUUM SOCKET BASE AND COLD MASS ASSY			
PROJECT OFFICE NATIONAL BUREAU OF STANDARDS METROLOGICAL DIVISION OF TECHNOLOGY 1010 GALLATIN AVENUE BETHESDA, MARYLAND 20815 4700-600			



ORIGINAL PAGE IS  
OF POOR QUALITY

REF. DWG. 3-4700-1200 SMT 1.3.4



SCALE  
0 2 4 6 8 10  
FEET


FRANCIS PETER  
NATIONAL MAGNET LABORATORY  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY  
MASSACHUSETTS  
DATE: 11/12/13  
BY: 11314  
DO NOT SCALE FOR CONSTRUCTION

REV	DESCRIPTION	BY	DATE	APPD
1	END-ETP 840 WWS POWER PLANT MAGNET SYSTEM			
2	VACUUM JACKET BASE AND COLD MASS ASSY			
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				



ORIGINAL PAGE 13  
OF POOR QUALITY

REF DWG J-4700-600 SHY 112




SECTION A-A


SCALE  
0 2 4 6 8 10  
FEET

REV	DESCRIPTION	BY	DATE	APPRO
1	ADD-ETP 80 MW POWER PLANT MAGNET SYSTEM			
2	VACUUM JACKET BASE AND COLD MASS ASSY			
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

FRANCIS PETER  
NATIONAL MAGNET LABORATORY  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY  
CAMBRIDGE, MASSACHUSETTS 02139  
PROJECT NO. J-4700-600  
DO NOT SCALE FROM THIS DRAWING



SECTION B-B





ORIGINAL PAGE IS  
OF POOR QUALITY

REF DWG. J-4700-600 BMT 142

FRANCIS B. TITUS NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY		REV	DESCRIPTION	BY	DATE	APPD
		TITLE:				
		MHD-ETP 800 MW POWER PLANT MAGNET SYSTEM				
		VACUUM JACKET BASE AND COLD MASS ASS'Y				
		DATE	BY	DATE	BY	DATE
		1-1-57	J. B. T.	1-1-57	J. B. T.	1-1-57
		J-4700-600				


LEFT AND RIGHT HAND COIL CONTAINER ASSY  
ARE JOINED BY WELDING HERE  
(INTERMITTENT WELD IS PERMISSIBLE)

REF ID: A66334

SCALE		1 2 3 4 5 6 7 8 9 10		FEET	
PLASMA PHYSICS LABORATORY MONSIEUR'S INSTITUTE OF TECHNOLOGY 1000 E. 10th Ave. S.W. Minneapolis, Minn. 55415 TEL. 612-325-1111 FAX 612-325-1111					


ORIGINAL PAGE IS  
OF POOR QUALITY

REF DWG 3-4100-601 SMT 143



REV		DESCRIPTION	BY	DATE	APPRO
A		WAS ADDED SERVICE SPACE ASSY, ITEM 17 AND ITEM 18	ML	8-8-84	
TITLE: 1400 KTF 200 MW POWER PLANT MAGNET SYSTEM					
COLD MASS ASSY					
FRANCIS BITTER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY 77 MASSACHUSETTS AVENUE CAMBRIDGE, MASSACHUSETTS 02139 617-253-2111 617-253-2112 617-253-2113 617-253-2114 617-253-2115 617-253-2116 617-253-2117 617-253-2118 617-253-2119 617-253-2120 617-253-2121 617-253-2122 617-253-2123 617-253-2124 617-253-2125 617-253-2126 617-253-2127 617-253-2128 617-253-2129 617-253-2130 617-253-2131 617-253-2132 617-253-2133 617-253-2134 617-253-2135 617-253-2136 617-253-2137 617-253-2138 617-253-2139 617-253-2140 617-253-2141 617-253-2142 617-253-2143 617-253-2144 617-253-2145 617-253-2146 617-253-2147 617-253-2148 617-253-2149 617-253-2150 617-253-2151 617-253-2152 617-253-2153 617-253-2154 617-253-2155 617-253-2156 617-253-2157 617-253-2158 617-253-2159 617-253-2160 617-253-2161 617-253-2162 617-253-2163 617-253-2164 617-253-2165 617-253-2166 617-253-2167 617-253-2168 617-253-2169 617-253-2170 617-253-2171 617-253-2172 617-253-2173 617-253-2174 617-253-2175 617-253-2176 617-253-2177 617-253-2178 617-253-2179 617-253-2180 617-253-2181 617-253-2182 617-253-2183 617-253-2184 617-253-2185 617-253-2186 617-253-2187 617-253-2188 617-253-2189 617-253-2190 617-253-2191 617-253-2192 617-253-2193 617-253-2194 617-253-2195 617-253-2196 617-253-2197 617-253-2198 617-253-2199 617-253-2200 617-253-2201 617-253-2202 617-253-2203 617-253-2204 617-253-2205 617-253-2206 617-253-2207 617-253-2208 617-253-2209 617-253-2210 617-253-2211 617-253-2212 617-253-2213 617-253-2214 617-253-2215 617-253-2216 617-253-2217 617-253-2218 617-253-2219 617-253-2220 617-253-2221 617-253-2222 617-253-2223 617-253-2224 617-253-2225 617-253-2226 617-253-2227 617-253-2228 617-253-2229 617-253-2230 617-253-2231 617-253-2232 617-253-2233 617-253-2234 617-253-2235 617-253-2236 617-253-2237 617-253-2238 617-253-2239 617-253-2240 617-253-2241 617-253-2242 617-253-2243 617-253-2244 617-253-2245 617-253-2246 617-253-2247 617-253-2248 617-253-2249 617-253-2250 617-253-2251 617-253-2252 617-253-2253 617-253-2254 617-253-2255 617-253-2256 617-253-2257 617-253-2258 617-253-2259 617-253-2260 617-253-2261 617-253-2262 617-253-2263 617-253-2264 617-253-2265 617-253-2266 617-253-2267 617-253-2268 617-253-2269 617-253-2270 617-253-2271 617-253-2272 617-253-2273 617-253-2274 617-253-2275 617-253-2276 617-253-2277 617-253-2278 617-253-2279 617-253-2280 617-253-2281 617-253-2282 617-253-2283 617-253-2284 617-253-2285 617-253-2286 617-253-2287 617-253-2288 617-253-2289 617-253-2290 617-253-2291 617-253-2292 617-253-2293 617-253-2294 617-253-2295 617-253-2296 617-253-2297 617-253-2298 617-253-2299 617-253-2300 617-253-2301 617-253-2302 617-253-2303 617-253-2304 617-253-2305 617-253-2306 617-253-2307 617-253-2308 617-253-2309 617-253-2310 617-253-2311 617-253-2312 617-253-2313 617-253-2314 617-253-2315 617-253-2316 617-253-2317 617-253-2318 617-253-2319 617-253-2320 617-253-2321 617-253-2322 617-253-2323 617-253-2324 617-253-2325 617-253-2326 617-253-2327 617-253-2328 617-253-2329 617-253-2330 617-253-2331 617-253-2332 617-253-2333 617-253-2334 617-253-2335 617-253-2336 617-253-2337 617-253-2338 617-253-2339 617-253-2340 617-253-2341 617-253-2342 617-253-2343 617-253-2344 617-253-2345 617-253-2346 617-253-2347 617-253-2348 617-253-2349 617-253-2350 617-253-2351 617-253-2352 617-253-2353 617-253-2354 617-253-2355 617-253-2356 617-253-2357 617-253-2358 617-253-2359 617-253-2360 617-253-2361 617-253-2362 617-253-2363 617-253-2364 617-253-2365 617-253-2366 617-253-2367 617-253-2368 617-253-2369 617-253-2370 617-253-2371 617-253-2372 617-253-2373 617-253-2374 617-253-2375 617-253-2376 617-253-2377 617-253-2378 617-253-2379 617-253-2380 617-253-2381 617-253-2382 617-253-2383 617-253-2384 617-253-2385 617-253-2386 617-253-2387 617-253-2388 617-253-2389 617-253-2390 617-253-2391 617-253-2392 617-253-2393 617-253-2394 617-253-2395 617-253-2396 617-253-2397 617-253-2398 617-253-2399 617-253-2400 617-253-2401 617-253-2402 617-253-2403 617-253-2404 617-253-2405 617-253-2406 617-253-2407 617-253-2408 617-253-2409 617-253-2410 617-253-2411 617-253-2412 617-253-2413 617-253-2414 617-253-2415 617-253-2416 617-253-2417 617-253-2418 617-253-2419 617-253-2420 617-253-2421 617-253-2422 617-253-2423 617-253-2424 617-253-2425 617-253-2426 617-253-2427 617-253-2428 617-253-2429 617-253-2430 617-253-2431 617-253-2432 617-253-2433 617-253-2434 617-253-2435 617-253-2436 617-253-2437 617-253-2438 617-253-2439 617-253-2440 617-253-2441 617-253-2442 617-253-2443 617-253-2444 617-253-2445 617-253-2446 617-253-2447 617-253-2448 617-253-2449 617-253-2450 617-253-2451 617-253-2452 617-253-2453 617-253-2454 617-253-2455 617-253-2456 617-253-2457 617-253-2458 617-253-2459 617-253-2460 617-253-2461 617-253-2462 617-253-2463 617-253-2464 617-253-2465 617-253-2466 617-253-2467 617-253-2468 617-253-2469 617-253-2470 617-253-2471 617-253-2472 617-253-2473 617-253-2474 617-253-2475 617-253-2476 617-253-2477 617-253-2478 617-253-2479 617-253-2480 617-253-2481 617-253-2482 617-253-2483 617-253-2484 617-253-2485 617-253-2486 617-253-2487 617-253-2488 617-253-2489 617-253-2490 617-253-2491 617-253-2492 617-253-2493 617-253-2494 617-253-2495 617-253-2496 617-253-2497 617-253-2498 617-253-2499 617-253-2500 617-253-2501 617-253-2502 617-253-2503 617-253-2504 617-253-2505 617-253-2506 617-253-2507 617-253-2508 617-253-2509 617-253-2510 617-253-2511 617-253-2512 617-253-2513 617-253-2514 617-253-2515 617-253-2516 617-253-2517 617-253-2518 617-253-2519 617-253-2520 617-253-2521 617-253-2522 617-253-2523 617-253-2524 617-253-2525 617-253-2526 617-253-2527 617-253-2528 617-253-2529 617-253-2530 617-253-2531 617-253-2532 617-253-2533 617-253-2534 617-253-2535 617-253-2536 617-253-2537 617-253-2538 617-253-2539 617-253-2540 617-253-2541 617-253-2542 617-253-2543 617-253-2544 617-253-2545 617-253-2546 617-253-2547 617-253-2548 617-253-2549 617-253-2550 617-253-2551 617-253-2552 617-253-2553 617-253-2554 617-253-2555 617-253-2556 617-253-2557 617-253-2558 617-253-2559 617-253-2560 617-253-2561 617-253-2562 617-253-2563 617-253-2564 617-253-2565 617-253-2566 617-253-2567 617-253-2568 617-253-2569 617-253-2570 617-253-2571 617-253-2572 617-253-2573 617-253-2574 617-253-2575 617-253-2576 617-253-2577 617-253-2578 617-253-2579 617-253-2580 617-253-2581 617-253-2582 617-253-2583 617-253-2584 617-253-2585 617-253-2586 617-253-2587 617-253-2588 617-253-2589 617-253-2590 617-253-2591 617-253-2592 617-253-2593 617-253-2594 617-253-2595 617-253-2596 617-253-2597 617-253-2598 617-253-2599 617-253-2600 617-253-2601 617-253-2602 617-253-2603 617-253-2604 617-253-2605 617-253-2606 617-253-2607 617-253-2608 617-253-2609 617-253-2610 617-253-2611 617-253-2612 617-253-2613 617-253-2614 617-253-2615 617-253-2616 617-253-2617 617-253-2618 617-253-2619 617-253-2620 617-253-2621 617-253-2622 617-253-2623 617-253-2624 617-253-2625 617-253-2626 617-253-2627 617-253-2628 617-253-2629 617-253-2630 617-253-2631 617-253-2632 617-253-2633 617-253-2634 617-253-2635 617-253-2636 617-253-2637 617-253-2638 617-253-2639 617-253-2640 617-253-2641 617-253-2642 617-253-2643 617-253-2644 617-253-2645 617-253-2646 617-253-2647 617-253-2648 617-253-2649 617-253-2650 617-253-2651 617-253-2652 617-253-2653 617-253-2654 617-253-2655 617-253-2656 617-253-2657 617-253-2658 617-253-2659 617-253-2660 617-253-2661 617-253-2662 617-253-2663 617-253-2664 617-253-2665 617-253-2666 617-253-2667 617-253-2668 617-253-2669 617-253-2670 617-253-2671 617-253-2672 617-253-2673 617-253-2674 617-253-2675 617-253-2676 617-253-2677 617-253-2678 617-253-2679 617-253-2680 617-253-2681 617-253-2682 617-253-2683 617-253-2684 617-253-2685 617-253-2686 617-253-2687 617-253-2688 617-253-2689 617-253-2690 617-253-2691 617-253-2692 617-253-2693 617-253-2694 617-253-2695 617-253-2696 617-253-2697 617-253-2698 617-253-2699 617-253-2700 617-253-2701 617-253-2702 617-253-2703 617-253-2704 617-253-2705 617-253-2706 617-253-2707 617-253-2708 617-253-2709 617-253-2710 617-253-2711 617-253-2712 617-253-2713 617-253-2714 617-253-2715 617-253-2716 617-253-2717 617-253-2718 617-253-2719 617-253-2720 617-253-2721 617-253-2722 617-253-2723 617-253-2724 617-253-2725 617-253-2726 617-253-2727 617-253-2728 617-253-2729 617-253-2730 617-253-2731 617-253-2732 617-253-2733 617-253-2734 617-253-2735 617-253-2736 617-253-2737 617-253-2738 617-253-2739 617-253-2740 617-253-2741 617-253-2742 617-253-2743 617-253-2744 617-253-2745 617-253-2746 617-253-2747 617-253-2748 617-253-2749 617-253-2750 617-253-2751 617-253-2752 617-253-2753 617-253-2754 617-253-2755 617-253-2756 617-253-2757 617-253-2758 617-253-2759 617-253-2760 617-253-2761 617-253-2762 617-253-2763 617-253-2764 617-253-2765 617-253-2766 617-253-2767 617-253-2768 617-253-2769 617-253-2770 617-253-2771 617-253-2772 617-253-2773 617-253-2774 617-253-2775 617-253-2776 617-253-2777 617-253-2778 617-253-2779 617-253-2780 617-253-2781 617-253-2782 617-253-2783 617-253-2784 617-253-2785 617-253-2786 617-253-2787 617-253-2788 617-253-2789 617-253-2790 617-253-2791 617-253-2792 617-253-2793 617-253-2794 617-253-2795 617-253-2796 617-253-2797 					

REF. DWG. J-4700-601 SAT 2





SCALE


0 2 4 6 8 10  
FEET

VIEW - 13

A	WAS ADDED SERVICE STACK ASSY.	ALL	8-28-87
	ITEM '17 AND ITEM '18		
REV	DESCRIPTION	BY	DATE APP'D
TITLE: MHD-ETP ROOM/NA POWER PLANT MAGNET SYSTEM			
COLD MASS ASSY			
ALL	7-28-87	10-2-87	4700-601

**FRANCIS BITTER**  
NATIONAL MAGNET LABORATORY  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

[illegible]

[illegible]



A.A. Brown  
J.P. x 10/10/68

[illegible]

ORIGINAL PAGE IS  
OF POOR QUALITY

SCALE

0 10 20 30 40 50 60 70 80 90 100  
INCHES







FRANCIS BITTER  
NATIONAL MAGNET LABORATORY  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY  
CAMBRIDGE, MASSACHUSETTS 02139  
U.S. GOVERNMENT PRINTING OFFICE  
1967 O-354-603

REV	DESCRIPTION	BY	DATE	APP.
1	NO. 177 200000 POWER PLAN			
2	MAGNET SYSTEM			
3	COIL CONTAINER AND INSULATION ASSY			
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				



ORIGINAL PAGE IS  
OF POOR QUALITY

REF DWG. 3-4700-603 BMT.1





SCALE  
0 24 48 72 96 120  
INCHES

REV	DESCRIPTION	BY	DATE	APPD.
TITLE: MAG-ETC ZUCONNA POWER PLANT MAGNET SYSTEM				
CURL CONTAINER AND INSULATION ASSY				
NO.	REV.	DATE	BY	APPD.
1	1	1-1-60	J	4700-603

FRANK B. BETER  
NATIONAL MAGNET LABORATORY  
BOSTON, MASSACHUSETTS INSTITUTE OF TECHNOLOGY

FOR INFORMATION: SEE DWG. 3-4700-603 BMT.1

[illegible]






A vertical scale bar is shown on the left side of the page. It is labeled "SCALE" at the top and "INCHES" at the bottom. The scale has markings at 0, 24, 48, 72, 96, and 120.

FRANCIS GITTER  
NATIONAL MAGNET LABORATORY  
MARSHALLS INSTITUTE OF TECHNOLOGY

REV	DESCRIPTION	BY	DATE	APPD
TITLE: MHD-ETG BORING POWER PLANT MAGNET SYSTEM				
COIL CONTAINER WELDMENT				

4700-604

REF ID: A634700-604 Sub. 3





SCALE

0 24 48 72 96 120

INCHES

[illegible]

ORIGINAL PAGE IS  
OF POOR QUALITY



REV	DESCRIPTION	BY	DATE	APPROVED
TITLE:				
MAGNETIC 200 MVA POWER PLANT MAGNET SYSTEM				
LAYER 2				
WINDING DETAIL				
<p>FRANCIS BETH NATIONAL BUREAU OF STANDARDS BETHESDA, MARYLAND</p> <p>DATE: 1970-12-10 BY: [Signature] CHECKED: [Signature] APPROVED: [Signature]</p>				
1 3-4700-605				

1-800-347-0044

SCALE

0 6 12 18 24 30

INCHES

FRANCIS BITTER  
NATIONAL MAGNET LABORATORY  
MSU - BURETT'S INSTITUTE OF TECHNOLOGY

REV	DESCRIPTION	BY	DATE	APPRO
TITLE: MMH-ETT ROOM MAG POWER PLANT MAGNET SYSTEM				
LAYER 'S WINDING DETAIL.				

DATE: 1/18/68



TIME: 1:30 PM

BY: [Signature]



17400-606

REFERENCE DRAWING  
1 J-4700-G02

ORIGINAL PAGE IS  
OF POOR QUALITY



FRANK BETER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY		TITLE: MHO EFF 800 MA POWER PLANT MAGNET SYSTEM		BY DATE APPR
JAN 28 1965		LAYER 25 WINDING DETAIL		
DO NOT SCALE FOR ORIENTATION		JAN 28 1965		14700-G07




SECTION B-B TOP MANIFOLDS  
SCALE: 1/2

ORIGINAL PAGE IS  
OF POOR QUALITY


REF. DWG. 3-4100-G13 SMT. 2 & 3



SECTION B-B  
SCALE: 1/2




SECTION A-A  
SCALE: 1/2



REV	DESCRIPTION	BY	DATE	APPD
1	MAN-ETP 3000NA POWER PLANT MAGNET SYSTEM			
TITLE				
OUTER THERMAL SHIELD				
FRANCIS B. BAKER NATIONAL MAGNET LABORATORY MAGNET SYSTEM				
3-4100-G13				


ORIGINAL PAGE IS  
OF POOR QUALITY



REV	DESCRIPTION	BY	DATE	APPRO
1	WIND UP ROOMS POWER PLANT MAGNET SYSTEM			
TITLE				
OFTER THERMAL SHIELD				
FRANCIS BITTER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY				
DESIGNED BY: J. B. BAKER CHECKED BY: J. B. BAKER DATE: 11/1/54 PROJECT NO. J-4700-G13 FOR CONSTRUCTION				




ORIGINAL PAGE IS  
OF POOR QUALITY



SCALE  
0 2 4 6 8 10 12 14 16 18 20  
INCHES

VIEW - [ ]

REF. DWG. J-4700-G13 SMT. 2




VIEW - [ ]

REV	DESCRIPTION	BY	DATE	APPD
1	INITIAL DESIGN	W. B. B.	10-1-60	
2	REVISION	W. B. B.	10-1-60	
3	REVISION	W. B. B.	10-1-60	
4	REVISION	W. B. B.	10-1-60	
5	REVISION	W. B. B.	10-1-60	
6	REVISION	W. B. B.	10-1-60	
7	REVISION	W. B. B.	10-1-60	
8	REVISION	W. B. B.	10-1-60	
9	REVISION	W. B. B.	10-1-60	
10	REVISION	W. B. B.	10-1-60	
11	REVISION	W. B. B.	10-1-60	
12	REVISION	W. B. B.	10-1-60	
13	REVISION	W. B. B.	10-1-60	
14	REVISION	W. B. B.	10-1-60	
15	REVISION	W. B. B.	10-1-60	
16	REVISION	W. B. B.	10-1-60	
17	REVISION	W. B. B.	10-1-60	
18	REVISION	W. B. B.	10-1-60	
19	REVISION	W. B. B.	10-1-60	
20	REVISION	W. B. B.	10-1-60	
21	REVISION	W. B. B.	10-1-60	
22	REVISION	W. B. B.	10-1-60	
23	REVISION	W. B. B.	10-1-60	
24	REVISION	W. B. B.	10-1-60	
25	REVISION	W. B. B.	10-1-60	
26	REVISION	W. B. B.	10-1-60	
27	REVISION	W. B. B.	10-1-60	
28	REVISION	W. B. B.	10-1-60	
29	REVISION	W. B. B.	10-1-60	
30	REVISION	W. B. B.	10-1-60	
31	REVISION	W. B. B.	10-1-60	
32	REVISION	W. B. B.	10-1-60	
33	REVISION	W. B. B.	10-1-60	
34	REVISION	W. B. B.	10-1-60	
35	REVISION	W. B. B.	10-1-60	
36	REVISION	W. B. B.	10-1-60	
37	REVISION	W. B. B.	10-1-60	
38	REVISION	W. B. B.	10-1-60	
39	REVISION	W. B. B.	10-1-60	
40	REVISION	W. B. B.	10-1-60	
41	REVISION	W. B. B.	10-1-60	
42	REVISION	W. B. B.	10-1-60	
43	REVISION	W. B. B.	10-1-60	
44	REVISION	W. B. B.	10-1-60	
45	REVISION	W. B. B.	10-1-60	
46	REVISION	W. B. B.	10-1-60	
47	REVISION	W. B. B.	10-1-60	
48	REVISION	W. B. B.	10-1-60	
49	REVISION	W. B. B.	10-1-60	
50	REVISION	W. B. B.	10-1-60	
51	REVISION	W. B. B.	10-1-60	
52	REVISION	W. B. B.	10-1-60	
53	REVISION	W. B. B.	10-1-60	
54	REVISION	W. B. B.	10-1-60	
55	REVISION	W. B. B.	10-1-60	
56	REVISION	W. B. B.	10-1-60	
57	REVISION	W. B. B.	10-1-60	
58	REVISION	W. B. B.	10-1-60	
59	REVISION	W. B. B.	10-1-60	
60	REVISION	W. B. B.	10-1-60	
61	REVISION	W. B. B.	10-1-60	
62	REVISION	W. B. B.	10-1-60	
63	REVISION	W. B. B.	10-1-60	
64	REVISION	W. B. B.	10-1-60	
65	REVISION	W. B. B.	10-1-60	
66	REVISION	W. B. B.	10-1-60	
67	REVISION	W. B. B.	10-1-60	
68	REVISION	W. B. B.	10-1-60	
69	REVISION	W. B. B.	10-1-60	
70	REVISION	W. B. B.	10-1-60	
71	REVISION	W. B. B.	10-1-60	
72	REVISION	W. B. B.	10-1-60	
73	REVISION	W. B. B.	10-1-60	
74	REVISION	W. B. B.	10-1-60	
75	REVISION	W. B. B.	10-1-60	
76	REVISION	W. B. B.	10-1-60	
77	REVISION	W. B. B.	10-1-60	
78	REVISION	W. B. B.	10-1-60	
79	REVISION	W. B. B.	10-1-60	
80	REVISION	W. B. B.	10-1-60	
81	REVISION	W. B. B.	10-1-60	
82	REVISION	W. B. B.	10-1-60	
83	REVISION	W. B. B.	10-1-60	
84	REVISION	W. B. B.	10-1-60	
85	REVISION	W. B. B.	10-1-60	
86	REVISION	W. B. B.	10-1-60	
87	REVISION	W. B. B.	10-1-60	
88	REVISION	W. B. B.	10-1-60	
89	REVISION	W. B. B.	10-1-60	
90	REVISION	W. B. B.	10-1-60	
91	REVISION	W. B. B.	10-1-60	
92	REVISION	W. B. B.	10-1-60	
93	REVISION	W. B. B.	10-1-60	
94	REVISION	W. B. B.	10-1-60	
95	REVISION	W. B. B.	10-1-60	
96	REVISION	W. B. B.	10-1-60	
97	REVISION	W. B. B.	10-1-60	
98	REVISION	W. B. B.	10-1-60	
99	REVISION	W. B. B.	10-1-60	
100	REVISION	W. B. B.	10-1-60	

ORIGINAL PAGE 13  
OF POOR QUALITY

REF DWG 3-4700-G14-SMT 2/3



SCALE  
0 24 48 72 96 120  
INCHES

FRANCIS BITTER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY		REV		DESCRIPTION	BY	DATE	APPRO
TITLE		AND CTF ROOMS POWER PLANT MAGNET SYSTEM		INNER THERMAL SHIELD			
DRAWN BY		CHECKED BY		DATE		APPRO	
3-4700-G14		3-4700-G14		3-4700-G14		3-4700-G14	

A horizontal scale bar with the word "SCALE" written vertically above it and "INCHES" written vertically below it. The scale has four major tick marks labeled "0", "24", "48", and "72" from left to right.


REF. DVG J. 4700-614 SMT 143

EXPANSION JOINT  
TYP  
SCALE: 1/2

[illegible]

ORIGINAL PAGE IS  
OF POOR QUALITY


HOLES FOR NUTS



SECTION B-B (TYP)  
SCALE: 1/2

N<sub>2</sub> GAS MANIFOLD

SEE SECTION A-A



LN<sub>2</sub> MANIFOLD

91 REF

VIEW - C

SCALE: 1:50

1/2 13 50C HD CAP SCR  
5/16 THK 5 STL CLAMP  
THERMAL SHIELD  
3/8-16 50C HD CAP SCR  
4-NEED  
5 STL RING  
WELDED TO WARM BORE

WARM BORE

SECTION A-A SUPPORT POST  
SCALE: 1/2 (TYP 60 PLACES)

REV	DESCRIPTION	BY	DATE	APPD
1	WHD-ETT ROOMA POWER PLANT MAGNET SYSTEM			
TITLE: INNER THERMAL SHIELD				
DATE	BY	DATE	BY	DATE
10-1-64	10-1-64	10-1-64	10-1-64	10-1-64
PROJECT NO. 4700-614				3-3


FRANCIS BITEER  
NATIONAL BUREAU OF STANDARDS  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

TECHNICAL DRAWING  
DRAWN BY: [illegible]  
CHECKED BY: [illegible]  
DATE: 10-1-64


FOR POST ROOMA POWER PLANT

**NOTE:**

- 1 DIM ARE FOR REF ONLY  
2 MAT'L - 304L  
3 ESTIMATED WEIGHT - 679,906 LBS




**SCALE**




REF. DWG J-4700-G15 ENT 2,3,4,4

[illegible]

ORIGINAL PAGE IS  
OF POOR QUALITY



SCALE




REF. DWG. 3 4700-615 DET. 1, 3, 4

REV.	DESCRIPTION	BY	DATE	APP'D
	MND-ETP 500 MW POWER PLANT MAGNET SYSTEM			
TITLE: VACUUM JACKET ASSY				
DATE	8-11-61	1-1-60	2-4	
				4700-615

FRANCIS BITTER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY	
DESIGNED BY: FRANCIS BITTER CHECKED BY: [illegible] APPROVED BY: [illegible] DO NOT SCALE FOR CONSTRUCTION	


ORIGINAL PAGE IS  
OF POOR QUALITY




VIEW B  
SCALE: 1/20

REF. DWG. 3-4700-615 BMT. 1


354.5 DIA COVER HEAD  
REF




SECTION A-A  
SCALE: 1/20



REV	DESCRIPTION	BY	DATE	APPD
1	MMO-ETP 200 MW POWER PLANT MAGNET SYSTEM			
TITLE: VACUUM JACKET ASSY				
FRANCIS BITTER NATIONAL BUREAU OF STANDARDS BETHESDA, MARYLAND 20815 PREPARED BY: [Signature] CHECKED BY: [Signature] DATE: 10/1/70 PROJECT: 3-4700-615				
DRAWN BY: [Signature] DATE: 10/1/70 PROJECT: 3-4700-615				



**SCALE**



FRANCIS BETER  
NATIONAL MAGNET LABORATORY  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

**DO NOT SCALE FOR CONSTRUCTION**

REV	DESCRIPTION	BY	DATE	APPD
TITLE: HHD-2.5 ROOMING POWER PLANT MAGNET SYSTEM				
VACUUM JACKET ASSY				
QTY	8.10.11	DATE	1.6.62	4-4
QTY	4700-615			

ORIGINAL PAGE IS  
OF POOR QUALITY

UNITED  
WELLS

30

REF ID: A66587

300 DIA --  
ACCESS HOLE  
TYPE 4-B

ON-SITE WELD

2230

15 TYP  
(REF)

30.

80  
TYPE

20

490 TVP 1490 TVP



The diagram illustrates a mechanical assembly, possibly a pump or engine component. It features a central circular chamber with internal components. Various parts are labeled with letters A through Z. A horizontal shaft or rod passes through the center of the chamber, with a handle or lever (A) on the left and a piston or plunger (B) on the right. The piston is connected to a crankshaft (C) and a connecting rod (D). The crankshaft is driven by a motor or engine (E) on the right. The entire assembly is mounted on a base (F). Other components include a valve (G), a piston (H), a connecting rod (I), a crankshaft (J), a motor (K), a base (L), a handle (M), a lever (N), a piston (O), a connecting rod (P), a crankshaft (Q), a motor (R), a base (S), a handle (T), a lever (U), a piston (V), a connecting rod (W), a crankshaft (X), a motor (Y), and a base (Z).

































[illegible]


ORIGINAL PAGE 19  
OF POOR QUALITY




SECTION C-C

REV. 2-17-60 - 1700-616

REV.	DESCRIPTION	BY	DATE
1	1700-616 POWER PLANT MAGNET SYSTEM		
TITLE: SERVICE STACK ASSY			
FRANCIS B. TITUS NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY CAMBRIDGE, MASS. 02139 1700-616-1700-616			




SECTION A-A



SECTION B-B

ORIGINAL PAGE IS  
OF POOR QUALITY

1. ALL DIMENSIONS ARE IN INCHES  
2. ALL DIMENSIONS ARE TO CENTER UNLESS OTHERWISE SPECIFIED  
3. ALL DIMENSIONS ARE TO CENTER UNLESS OTHERWISE SPECIFIED



SCALE




INCHES

REV	DESCRIPTION	BY	DATE	APPRO
TITLE: MHD-CTY 200MW POWER PLANT MAGNET SYSTEM				
SUB-STRUCTURE DETAIL, STRAIGHT				
FRANCIS BITTER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY TELEPHONE: 617-253-2900 FAX: 617-253-2900 DO NOT SCALE FOR CONSTRUCTION				
4700-300				4700-300

NOTE: THIS DRAWING WAS PREPARED  
ON 10-10-60 BY  
1. 10-10-60


ORIGINAL PAGE IS  
OF POOR QUALITY



SCALE  
0 1 2 3 4 5 6  
INCHES


REV	DESCRIPTION	BY	DATE	APPRO
TITLE: HMD ETT 200MB POWER PLANT MAGNET SYSTEM				
SUB: STRUCTURE DETAIL, STRAIGHT				
FRANCIS BITTER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY VOLUNTARILY MADE AVAILABLE DATE 10-10-60 BY 10-10-60 DO NOT SCALE FOR CONSTRUCTION				
4700-300				

NOTE: 1. VALUES SHOWN ARE APPROXIMATE  
OF THE TOTAL NUMBER OF TUBES  
THE OTHER MAY INVOLVE HAND  
2. REF CNG 3-4700-502  
3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100. 101. 102. 103. 104. 105. 106. 107. 108. 109. 110. 111. 112. 113. 114. 115. 116. 117. 118. 119. 120. 121. 122. 123. 124. 125. 126. 127. 128. 129. 130. 131. 132. 133. 134. 135. 136. 137. 138. 139. 140. 141. 142. 143. 144. 145. 146. 147. 148. 149. 150. 151. 152. 153. 154. 155. 156. 157. 158. 159. 160. 161. 162. 163. 164. 165. 166. 167. 168. 169. 170. 171. 172. 173. 174. 175. 176. 177. 178. 179. 180. 181. 182. 183. 184. 185. 186. 187. 188. 189. 190. 191. 192. 193. 194. 195. 196. 197. 198. 199. 200. 201. 202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225. 226. 227. 228. 229. 230. 231. 232. 233. 234. 235. 236. 237. 238. 239. 240. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832



ME: 1/2/2011 11:30 AM


**SCALE**



SCALE _____		1 2 3 4 5 6 8 10 12	
INCHES			
FRANCIS BUITER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY		SUB-STRUCTURE DETAIL, CORNER	
UNIVERSITY MICROFILMS SERIALS ACQUISITION 300 N. ZEEB RD. ANN ARBOR MI 48106 SERIALS ACQUISITION UNIVERSITY MICROFILMS 300 N. ZEEB RD. ANN ARBOR MI 48106		DATE: 11/11/81 BY: [Signature] 4700-301	
DO NOT SCALE FOR CONSTRUCTION			
REV		DESCRIPTION	
BY		DATE/APPD	
TITLE: 440-21F 2000VA POWER PLANT MAGNET SYSTEM			

ORIGINAL PAGE IS  
OF POOR QUALITY

NOTE:  
1. SEE ASSEMBLY TO  
2. SEE ASSEMBLY TO  
3. SEE ASSEMBLY TO  
4. SEE ASSEMBLY TO  
5. SEE ASSEMBLY TO  
6. SEE ASSEMBLY TO  
7. SEE ASSEMBLY TO  
8. SEE ASSEMBLY TO  
9. SEE ASSEMBLY TO  
10. SEE ASSEMBLY TO






REV	DESCRIPTION	BY	DATE	APPD
1	WIND-RTF 200 MVA POWER PLANT MAGNET SYSTEM			
2	SUB-STRUCTURE DETAIL CURVED			
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

FRANCIS BITTER  
NATIONAL MAGNET LABORATORY  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY  
77 MASSACHUSETTS AVENUE  
CAMBRIDGE, MASSACHUSETTS 02139  
U.S.A.  
DO NOT SCALE FOR CONSTRUCTION

ORIGINAL PAGE IS  
OF POOR QUALITY

NOTES:  
1. SEE DRAWING 400-100-100  
2. SEE DRAWING 400-100-100  
3. SEE DRAWING 400-100-100  
4. SEE DRAWING 400-100-100  
5. SEE DRAWING 400-100-100



SEE DRAWING 400-100-100

SECTION A-A  
SEE DRAWING 400-100-100



REV.	DESCRIPTION	BY	DATE
1	REVISION		
TITLE: RING-CLIP BRIDGING POWER PLANT MAGNET SYSTEM			
SUB-STRUCTURE DETAIL CURVED			
FRANCIS B. OTTER NATIONAL MAGNET LABORATORY MASSACHUSETTS INSTITUTE OF TECHNOLOGY CAMBRIDGE, MASSACHUSETTS 02139 DRAWN BY: [Name] CHECKED BY: [Name] DATE: [Date] NO. 400-100-100			

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----